email: urihydraulic@gmail.com

Allotment Order No. 10 of 06/2024

Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 08 of 06/2024

M/S	:	**GANAI CONSTRUCTION AND SERVICES PRIVATE LIMITED**
R/O	:	**Rajurwani Uri**
Registration No.	:	**U501007K2020PTC01199**
TIN No./GST No:-	:	**01AA1CG7124L1ZO**
Name of work	:	***Construction of Water Supply Scheme Latimar Garkote by way of Construction of Intake Chambers/Chowkidar quarter Protection works, , laying and fitting of GI Pipes and other allied works (for providing 100% FHTC) under JJM***
eNIT No.	:	**23 /Hyd/Uri of 2023-24** TENDER ID 2023_IFC_244188_11
Your Tender Received in response to	:	eNIT No:23/Hyd/Uri_of_2023-24 Dated: 31/07/2023 issued under endorsement No:- HDU/CC-02/3061-72 Dated: 31/07/2023 (S. No: 11) Tender ID : 2023_IFC_244188_11
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/eNIT-23/3655-57 Dated:- 22/08/2023*** ***(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/8440-53 Dated:- 31/10/2023***
Ref: to AAA	:	**Accorded vide Order No. CE/PHE/DB/540 of 08/2022 Dated:- 31/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/201of 08/2022 Dated:- 31/08/2022.**
LOI Issued under No:-	:	**NIT No. 23/5307-08 Dated:- 31/10/2023**
Advertisement cost	:	**Rs: 74.08 Lacs**
Allotted cost	:	**₹ 8111419.04** **Rupees Eighty One Lakh(s) Eleven Thousand Four Hundred Nineteen And Paise Four Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	**Bid Security Declaration Format**
Name of the Bank	:	

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

XEN-

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri
(Syed Shafat

NO: HDU/CC-04/ 807-19

DATED: 20-06-2024

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**

2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**

3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**

4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/8440-53 Dated:- 31/10/2023**

5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**

6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**

7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**

8 **Chief Planning Officer Baramulla(Member DJJM) for information.**

9 **Chief Medical Officer Baramulla(Member DJJM) for information.**

10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.**

11 **District Information Officer Baramulla (Member DJJM) for information.**

12 **Assistant Executive Engineer PHE Sub Division Uri for information.**

13 **File.**

Government of Jammu and Kashmir

Annexure "A" to the Allotment Order No. 08 of 06/2023

Construction of Water Supply Scheme Latimar Garkote by way of Construction of Intake Chambers/Chowkidar quarter Protection works, , laying and fitting of GI Pipes and other allied works (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5Mtr in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils	3164.760	Cum	590.588	**1869070.07**
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	2620.750	Cum	217.577	**570213.61**
3	Providing and laying stone soling 2nd class incl. cost of stones	25.020	Cum	674.958	**16887.45**
4	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	16.330	Cum	5323.715	**86936.26**
5	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 3 : 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40-mm nominal size) crushed.	29.000	Cum	5954.325	**172675.43**
6	Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	25.780	Cum	7079.383	**182506.50**
7	Providing and laying in position specified grade of reinforced cement concrete including cuirring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	11.060	Cum	8541.832	**94472.66**
8	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	13.850	Cum	10301.902	**142681.35**
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	0.600	Cum	10785.027	**6471.02**
10	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	51.000	Cum	2737.500	**139612.50**
11	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	**0.00**
11.1	Foundations, footings, bases of columns	38.600	Sqm	287.219	**11086.63**
11.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	286.160	Sqm	628.366	**179813.14**

11/6

S#	Particulars	Qty	Unit	Rate	Amount
11.3	Suspended floors, roofs, landings, balconies and access platform.	62.810	Sqm	695.982	43714.63
11.4	Lintel Beams	10.270	Sqm	550.621	5654.88
11.5	Edges of Slab	117.000	mtr	265.319	31042.26
12	12mm cement plaster of mix 1:4	407.210	Sqm	392.010	159630.39
13	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	200.000	Kg	74.033	14806.59
14	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1090.000	Kg	111.843	121909.20
15	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	2167.000	Kg	111.843	242364.43
16	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	3010.000	Kg	95.451	287307.96
17	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	76.740	Kg	111.843	8582.85
18	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.50 mmthick with 20mm nominal size stone aggregate. Crushed	42.360	Sqm	608.273	25766.42
19	Providing and lying 50mmthick DPC with cement concrete 1: 2: 4 and curing complete	24.000	Sqm	448.950	10774.80
20	Providing woodwork in frames of doors, windows, celestory, windows and other frames, wrought frames and fixed in position with hold fast lugs with dash fastness of required dia and length (hold fast lugs or with dash fastness shall be paid for separately Second Class Kail Wood	0.750	Cum	100811.558	75608.67
21	Brick work with common burnt clay F.P.S.(non-modualar) bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement:6 coarse sand)	22.210	Cum	8220.603	182579.59
22	Providing and fixing 35mm panelled or pannelled glazed shutter for doors, windows ad celestory widows including ISI Marked, M.S Pressed, but hinges, bright finished of required size with necessary screws excl. pannelling which will be paid for separately all complete.	9.610	Sqm	3387.711	32555.90
23	Providing and fixing paneling or panelig & glazing in pannelled & glazed shutter for doors, windows & clear stove windows. (Area of opening for pannel inserts excluding position inside groves or rebates to be measured). Pannelling for pannelled or panelled glazed shutters Decorative ply wood both sides decorative vaneer and ommericla vane or other type conformig to IS 1328 BWR Tp. (Including all sorts of carriages upto site of work)	7.230	Sqm	2114.664	15289.02
24	Providing and fixing glazed shutters for doors, windows and celestory windows using 10Kg/Sqm (4mm Thick) float glass panes including ISI Marked M.S Pressed but hinges bright finished of requuired size with necessary screws. (Including all sorts of carriages upto site of work)	7.350	Sqm	4080.025	29988.18

P 2/6

S#	Particulars	Qty	Unit	Rate	Amount
25	Providing and fixing 35 mm thick wire gauze shutters using galvanised M.S. wire gauze of average width for aperture 1.4 mm in both directoin with wire of dia. 0.63 mm for doors, windows and clerestory windows with hinges and necessary screws, Second class kail wood. (Including all sorts of carriages upto site of work)	9.000	Sqm	3998.557	**35987.01**
26	Providing and laying of 1st quality ceramic glazed wall/floor tiles conforming to IS 13753 of minimum thick ness 5mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalnet nake in all colours, shades except bergundy , bottle green black of any size as approved by Engineer Incharge laid on 20mm thick bed of cement cmortar (1:4) including pointing the joints with white cement and matching pigments etc complete.	37.000	Sqm	1331.575	**49268.27**
27	Flooring with marble stone of specified thickness as per sampleof marble approved by Engineer Incharge over 20mm (average) thick base of cement mortar 1:4 (1 Cement 4: crse sand) laid and jointed with grey cement slurry including rubbing, polishing and curing complete with Udaipur Green Marble	4.180	Sqm	2416.063	**10099.14**
28	Finishing walls with water proofing cement paint (Two or more coats) Work applied @3.84Kg/10Sqm	101.000	Sqm	100.521	**10152.62**
29	Applying One coat of Cement Primer of approved brand manufacture on wall shape	101.000	Sqm	64.988	**6563.81**
30	Applying Priming coat with ready mixed primer of approved brand and manufacture on wood work (hard and soft wood	37.000	Sqm	65.153	**2410.64**
31	Painting with synthetic enamel paint of approved brand and manufacture 2 or more coats on new works	37.000	Sqm	133.535	**4940.80**
32	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case raklling and similar works and applying primer coat	21.000	Kg	190.804	**4006.88**
33	Providing and fixing of Pre colour coated galvanized iron sheets (Size, shape and pitch of corrugationas approved by Engineer Incharge at site (0.5mmThick) including self driling , self tapping , Screw, EPDM seal or with Ploymer coated J ort L hooks, bolts, and nuts etc inclusing ridges/valleys of rquired width as aaproved by Engineeer Incharge at site	88.000	Sqm	909.124	**80002.89**
34	Providing and fixing of plained eves boarding 250X32mm nominal size (Kail wood)	37.500	RM	759.821	**28493.27**
35	Providing ridges or hips of width 60com overall width plain G.S Sheets fixed with Plymer coated J or L hooks, bolts and coating not less than 275 gram/m2 limpet and bitumen washers complete	10.670	RM	757.028	**8077.49**
36	Providing and fixing of hold fasts embebed in concrete	38.000	Kgs	122.640	**4660.32**
37	Providing and fixing of water closet (Indian Type) squatting pan with 10mm dia PR s trap fluhing cistern with handle lower with all fittings and fixtures	1.000	No	5543.438	**5543.44**
38	Supply and filling in plinth level with fine sand under floor including watering ramming consoldating and dresing complete	18.000	Cum	862.203	**15519.65**
39	Providing and fixing of soil, waste and went pipes			0.000	**0.00**
39.1	10mmDia Pipe	20.000	M	984.263	**19685.25**
39.2	75mm dia pipe	15.000	M	845.471	**12682.07**
40	Providing and Fixing white viterous China pedestal for wash basin completely recesed at back for reception of pipes and fittings	1.000	No	1367.929	**1367.93**
41	Stainless Steel Kitchen sink with CI brackets and plug 40mm with drain board.	1.000	No	3359.602	**3359.60**
42	PVC waste pipe for sink and wash basin 40mm semi right	2.000	No	85.410	**170.82**

P3/6

S#	Particulars	Qty	Unit	Rate	Amount
43	Trap for self cleaning design with hinded grating	2.000	No	846.983	1693.97
44	600mm long towel rail	1.000	No	328.500	328.50
45	Providing and fixing of 450X450 main hole cover and frame for septic tank	4.000	No	657.000	2628.00
46	Providing and fixing of chlorinated olyviml Chloride (CPVC) pipes having thermal stability for hot and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer incharge	36.000	No	256.394	9230.19
47	Providing and fixing of electric wiring 3/22 for electric point through conduit (lighting)(including switch,scokets condiut wiring complete job	20.000	Point	2463.750	49275.00
48	Providing and fixing of electric wiring 7/20 for electric points (including switch,scokets condiut wiring complete job	10.000	Point	4106.250	41062.50
49	Providing and fixing of MCB mounted on wall as requried at site complete job	4.000	Point	1642.500	6570.00
50	Providing and fixing of mirror of superior (approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board baking (recanguler shape 453*357mm	2.000	No	1204.500	2409.00
51	Providing and fixinng of 600x120mm x 5mm glass shelf with edegs round of supported on anodise aluminium angle frame with cp brass brackest and guard rail complete fixed with 40mm long screws complete job	1.000	No	930.750	930.75
52	Providing and fixing of bends of required degree with excee door,insertion rubber insertion etc			0.000	0.00
52.1	100mm dia	4.000	No	580.350	2321.40
52.2	75mm dia	4.000	No	383.250	1533.00
53	Providing and fixing double equal junction of required degree			0.000	0.00
53.1	100mm dia	3.000	No	876.000	2628.00
53.2	75mm dia	3.000	No	766.500	2299.50
54	Providing and fixing of floor trapes			0.000	0.00
54.1	100 mm dia	2.000	No	1040.250	2080.50
54.2	75mm dia	1.000	No	854.100	854.10
55	Supplying and filling in plinth with fine sand under floors including, watering, ramming, consolidating and dressing complete	17.280	cum	862.203	14898.87
56	Providing ridges or hips of width 60cm overall width plain G.S. sheets fixed with polymer coated J. or L hooks, bolts and nuts 8mm dia G.I. limpet and bitumen washers complete0.63 mm thick with zinc coating not less than 275 gram/m2	10.670	mtr	757.028	8077.49
57	Providing and fixing plained eaves boarding.250x32 mm (nominal size)	37.500	mtr	759.821	28493.27
58	Providing and applying white cement based putty of specified thickness, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete 2mm thick.	89.550	sqm	188.778	16905.07
59	Providing and fixing of water heating gysers I.S.I Mark standard quality 50 liter capacity with inlet outlet connection and electric connection complete job	1.000	No	9307.500	9307.50
60	Providing and fixing of hardware items,i.e handles tower bolts locking arrangement etc as per the direction of in charge engineer complete Job	1.000	Job	32850.000	32850.00

Pg/6

Allotment Order No. 10 **of** 06/2024

M/S : Naveed & Co.

S#	Particulars	Qty	Unit	Rate	Amount
61	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
61.1	50mm dia	2.000	Nos	4380.000	8760.00
62	Providing and fixing of 8mm thick MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carraiges upto site of work complete job.			0.000	0.00
62.1	80mm dia	16.000	Joints	1314.000	21024.00
62.2	65mm dia	258.000	Joints	1204.500	310761.00
62.3	50mm dia	242.000	Joints	1095.000	264990.00
62.4	40mm dia	306.000	Joints	985.500	301563.00
63	Laying and fitting of GI Pipes with GI fitting excluding trenching and refilling etc.			0.000	0.00
63.1	65 mm dia GI pipes	3600.000	Mtr	79.990	287963.10
63.2	50 mm dia GI pipes	3800.000	Mtr	44.676	169768.80
63.3	40 mm dia GI pipes	4000.000	Mtr	44.676	178704.00
63.4	25 mm dia GI pipes	3000.000	Mtr	33.562	100685.25
63.5	20 mm dia GI pipes	3000.000	Mtr	22.174	66521.25
63.6	15mm dia GI pipes	2000.000	Mtr	22.174	44347.50
64	Making connection of GI distribution branch with GI main of following sizes, by P/F of tees, incld. cutting and threading the pipe etc. complete			0.000	0.00
64.1	25 to 40 mm dia nominal bore	160.000	No	729.544	116727.00
64.2	Above 40 mm nominal bore	80.000	No	1389.281	111142.50
65	Providing and Fixing 4mm GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	117.000	Sqm	803.183	93972.35
66	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	714.840	kg	111.843	79950.06
67	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete.	288.000	kg	111.843	32210.87
68	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
68.1	Cement and Steel (60Kms)	114.620	Mton	778.457	89226.79
68.2	Sand. (70Kms)	52.210	Cum	984.504	51400.93
68.3	Agg. 20mm (115Kms)	65.800	Cum	1528.390	100568.07
68.4	Agg. 40mm (115Kms	12.590	Cum	1661.279	20915.51
68.5	Stone Soling (7KM)	19.820	Cum	304.082	6026.90
68.6	Bricks (135Kms)	11105.000	No	4.665	51801.49
68.7	Timber (45Kms)	0.740	Cum	1249.888	924.92

PS/4

Allotment Order No. 10 of 06/2024

M/S : Naveed & Co.

S#	Particulars	Qty	Unit	Rate	Amount
69	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
69.1	Cement (1000Mtrs)	29.980	Mton	504.204	15116.03
69.2	Steel (1000Mtrs)	30.120	Mton	1083.108	32623.22
69.3	Pipe (1000Mtrs)	53.790	Mton	1083.108	58260.40
69.4	Sand. (1000Mtrs)	52.210	Cum	1180.651	61641.78
69.5	Agg. 20mm (1000Mtrs)	65.800	Cum	1180.651	77686.83
69.6	Agg. 40mm (1000Mtrs)	12.590	Cum	1276.321	16068.88
69.7	Stone Soling (500Mtrs)	19.820	Cum	800.226	15860.48
69.8	Bricks (1000Mtrs)	11105.000	No	2.190	24319.95
69.9	Timber (1000Mtrs)	0.740	Cum	696.289	515.25
				Total	8111419.04

Rupees Eighty One Lakh(s) Eleven Thousand Four Hundred Nineteen And Paise Four Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri

P4/6