**Government of Jammu and Kashmir**

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

# Allotment Order No. 20 of 08/2024

| | | |
|---|---|---|
| **M/S** | : | **Salfi Constructions** |
| **Prop:** | : | **Mohammad Yousuf Sofi** |
| **S/O** | : | **Abdul Jabar Sofi** |
| **R/O** | : | **Rangwar Baramulla** |
| **Registration No.** | : | **001/AYY/Civil Sanitary/CE/CID/2017-18** |
| **TIN No./GST No:-** | : | **01CNAPS7081N1ZO** |
| Name of work | : | ***Construction of Water Supply Scheme Latimar Garkote by way of Construction/Commissioning and Testing of PSTs/ SRs/SSFPs/, Chain Link fencing, and other allied works (for providing 100% FHTC) under JJM*** |
| **eNIT No.** | : | **43/Hyd/Uri of 2023-24** TENDER ID 2023_IFC_233715_5 |
| **Your Tender Received in response to** | : | eNIT No: 43/Hyd/Uri_of_2023-24 Dated: 16/10/2023 issued under endorsement No:- HDU/CC-02/4746-57 Dated: 16/10/2023 (S. No: 06) Tender ID : 2023_IFC_233715_5 |
| **Reference** | : | ***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.***<br>***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.***<br>***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.***<br>***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.***<br>***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).***<br>***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.***<br>***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.***<br>***(viii) This Office Letter No: HDU/NIT-43/7661-62 Dated:- 11/03/2024***<br>***(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/1442-55 Dated:- 15/06/2024*** |
| Ref: to AAA | : | **Accorded vide Order No. CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.** |
| Ref: to Tech. Sanction | : | **Accorded vide Order No. CE/PHE/DB/201 of 08/2022 Dated:- 31/08/2022** |
| LOI Issued under No:- | : | **NIT NO. 43/735-36Dated:- 20/06/2024** |
| Advertisement cost | : | **Rs: 101.53 Lacs** |
| Allotted cost | : | **₹ 11656912.65** **Rupees One Crore Sixteen Lakh(s) Fifty Six Thousand Nine Hundred Twelve And Paise Sixty Five Only** |
| Time of completion | : | 120-days |
| M.H. of Account | : | **(JJM)** |
| Ref. To CDR No. | : | **BSDF** |
| Name of the Bank | : | |

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

**Allotted Rates as "Annexure A" Enclosed"**

**Terms and Conditions:-**

1 Time of completion is essence of the contract.

XEN

Scanned with OKEN Scanner

ne work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri
(Syed Shafat

**NO: HDU/CC-04/** 1657-69

**DATED:** 14-08-2024

**Copy to the:**

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**

2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**

3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**

4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/1442-55 Dated:- 15/06/2024**

5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**

6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**

7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**

8 **Chief Planning Officer Baramulla(Member DJJM) for information.**

9 **Chief Medical Officer Baramulla(Member DJJM) for information.**

10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.**

11 **District Information Officer Baramulla (Member DJJM) for information.**

12 **Assistant Executive Engineer PHE Sub Division Uri for information.**

13 **File.**

Scanned with OKEN Scanner

## Annexure "A" to the Allotment Order No. 20 of 08 /2024

*Construction of Water Supply Scheme Latimar Garkote by way of Construction/Commissioning and Testing of PSTs/ SRs/SSFPs/, Chain Link fencing, and other allied works (for providing 100% FHTC) under JJM*

| S# | Particulars | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|
| 1 | Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge | | | | |
| 1.1 | In all kinds of soils | 971.940 | Cum | 620.253 | 602848.21 |
| 2 | Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m. | 162.820 | Cum | 228.505 | 37205.18 |
| 3 | Providing and laying stone soling 2nd class incl. cost of stones | 67.660 | Cum | 708.860 | 47961.47 |
| 4 | Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed. | 45.090 | Cum | 5591.116 | 252103.42 |
| 5 | Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size) | 144.760 | Cum | 7434.969 | 1076286.04 |
| 6 | Providing and laying in position specified grade of reinforced cement concrete including cuirring but excluding cost centering shuttering finishing and reinforcement ( all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed | 73.330 | Cum | 8970.874 | 657834.19 |
| 7 | Reinforced Cement concrete work in wall ( any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size. | 96.100 | Cum | 10819.350 | 1039739.49 |
| 8 | Reinforced cement concrete work in beams, suspended floors, roofs having slope upto $15^0$ landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3( 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size) | 8.600 | Cum | 11326.741 | 97409.97 |
| 9 | Providing and fixing upto floor five level precast cement concrete string or lacing, courses copings bed plates anchor blocks plain window sills, shelves, louvers, steps stair cases etc including hoisting and setting fr psition with cement mortar 1:3 (1 cement: 3 coarse sand) cost of required centring shuttering and curing complete I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) | 0.982 | Cum | 9980.850 | 9801.19 |
| 10 | Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement | 11.660 | Cum | 11965.198 | 139514.21 |
| 11 | Centering and shuttering including strutting propping etc. and removal of Form work for. | | | 0.000 | 0.00 |
| 11.1 | Foundations, footings, bases of columns | 47.850 | Sqm | 301.645 | 14433.71 |
| 11.2 | Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc. | 1371.810 | Sqm | 659.928 | 905295.14 |

Scanned with OKEN Scanner

| # | Particulars | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|
| 11.3 | Suspended floors, roofs, landings, balconies and access platform. | 68.030 | Sqm | 730.940 | 49725.85 |
| 11.4 | Arches, Domes, walls upto 60 mtr span | 90.340 | Sqm | 2399.820 | 216799.74 |
| 11.5 | Columns, Pilers, abutment, posts and struts. | 25.200 | Sqm | 782.173 | 19710.75 |
| 12 | 12mm cement plaster of mix 1:4 | 1106.250 | Sqm | 411.700 | 455443.13 |
| 13 | Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete | 935.000 | Kg | 77.752 | 72697.65 |
| 14 | Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job. | 817.500 | Kg | 117.461 | 96024.37 |
| 15 | Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. | 1637.530 | Kg | 117.461 | 192345.91 |
| 16 | Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars. | 17381.290 | Kg | 100.246 | 1742396.11 |
| 17 | Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site. | 534.520 | Kg | 117.461 | 62785.25 |
| 18 | Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work) | | | 0.000 | 0.00 |
| 18.1 | 80mm dia | 4.000 | Nos | 6900.000 | 27600.00 |
| 18.2 | 65mm dia | 2.000 | Nos | 5750.000 | 11500.00 |
| 18.3 | 50mm dia | 2.000 | Nos | 4600.000 | 9200.00 |
| 18.4 | 40mm dia | 4.000 | Nos | 4025.000 | 16100.00 |
| 19 | Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality | | | 0.000 | 0.00 |
| 19.1 | 80mm dia | 8.000 | Nos | 1035.000 | 8280.00 |
| 19.2 | 50mm dia | 18.000 | Nos | 805.000 | 14490.00 |
| 20 | Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia ength | 40.000 | No | 230.000 | 9200.00 |
| 21 | Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job. | 122.400 | Cum | 9775.000 | 1196460.00 |
| 22 | Providing and fixing of 8mm MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carraiges upto site of work complete job. | | | 0.000 | 0.00 |
| 22.1 | 80mm dia | 45.000 | Joints | 1380.000 | 62100.00 |
| 22.2 | 65mm dia | 45.000 | Joints | 1265.000 | 56925.00 |
| 22.3 | 50mm dia | 90.000 | Joints | 1150.000 | 103500.00 |
| 23 | Providing and Fixing 4mm GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site. | 373.040 | Sqm | 843.525 | 314668.57 |
| 24 | Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete | 2526.870 | kg | 117.461 | 296808.68 |

Scanned with OKEN Scanner

| | Particulars | Qty | Unit | Rate | Amount |
|---|---|---|---|---|---|
| 25 | Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete. | 1472.400 | kg | 117.461 | 172949.58 |
| 26 | Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer | | | 0.000 | 0.00 |
| 26.1 | Cement and Steel (60Kms) | 154.110 | Mton | 817.558 | 125993.86 |
| 26.2 | Sand. (70Kms) | 178.320 | Cum | 1033.954 | 184374.59 |
| 26.3 | Agg. 20mm (115Kms) | 266.120 | Cum | 1548.140 | 411991.02 |
| 26.4 | Agg. 40mm (115Kms | 40.600 | Cum | 1654.000 | 67152.40 |
| 26.5 | Stone Soling (7KM) | 67.600 | Cum | 314.000 | 21226.40 |
| 27 | Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer | | | 0.000 | 0.00 |
| 27.1 | Cement (1000Mtrs) | 129.840 | Mton | 529.529 | 68754.05 |
| 27.2 | Steel (1000Mtrs) | 23.700 | Mton | 1137.511 | 26959.01 |
| 27.3 | Sand. (1000Mtrs) | 178.320 | Cum | 1239.953 | 221108.42 |
| 27.4 | Agg. 20mm (1000Mtrs) | 266.120 | Cum | 1239.953 | 329976.29 |
| 27.5 | Agg. 40mm (1000Mtrs) | 40.600 | Cum | 1340.429 | 54421.42 |
| 27.6 | Stone Soling (500Mtrs) | 67.600 | Cum | 840.420 | 56812.39 |
| | | | | *Total* | 11656912.65 |

*Rupees One Crore Sixteen Lakh(s) Fifty Six Thousand Nine Hundred Twelve And Paise Sixty Five Only*

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri

Scanned with OKEN Scanner