Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 134 of 10/2023

M/S	:	BALOTE CONSTRUCTIONS COMPANY
Prop.	:	Mohammad Ashraf Balote
S/O	:	Qammar-ud-din Balote
R/O	:	Garkote Uri
Registration No.	:	117/AYY/CE/CID/PDC/2010-11
TIN No./GST No:-	:	01ANAPA7383B1ZS

Name of work : *Construction of Water Supply Scheme Lower Nambla by way of Construction/ Commissioning and Testing of Intake Chambers /SSFPs/ Protection works, Chain Link fencing, and other allied works (for providing 100% FHTC)*

eNIT No. : **05/Hyd/Uri of 2023-24** TENDER ID 2023_IFC_210282_27

Your Tender Received in response to : eNIT No:05/Hyd/Uri_of_2023-24 Dated: 17/05/2023 issued under endorsement No:- HDU/CC-02/355-66 Dated: 24/04/2023 (S. No: 27) Tender ID : 2023_IFC_210282_27

Reference :

(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.

(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.

(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.

(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.

(viii) This Office Letter No: HDU/eNIT-05/ 3130-31 Dated:- 31/07/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5037-50 Dated: 04/08/2023

Ref: to AAA	:	**Accorded vide Order No. 38/SE/HYD/DB/JJM of 2022-23 Dated:- 26/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/558 of 09/2022 Dated:- 10/09/2022.**
LOI Issued under No:-	:	**NIT NO. 05/3294-95 Dated:- 08/08/2023**
Advertisement cost	:	**Rs: 52.83 Lacs**
Allotted cost	:	**₹ 5727462.23** **Rupees Fifty Seven Lakh(s) Twenty Seven Thousand Four Hundred Sixty Two And Paise Twenty Three Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	**BSDF:**
Name of the Bank	:	

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN

The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by

Head Draftsman

Executive Engineer
Hydraulic Division Uri
Syed Shafat

NO: HDU/CC-04/ 5061-73

DATED: 21-10-2023.

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**

2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**

3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**

4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5037-50 Dated: 04/08/2023**

5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**

6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**

7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**

8 **Chief Planning Officer Baramulla(Member DJJM) for information.**

9 **Chief Medical Officer Baramulla(Member DJJM) for information.**

10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**

11 **District Information Officer Baramulla (Member DJJM) for information.**

12 **Assistant Executive Engineer PHE Sub Division Uri for information.**

13 **File.**

Annexure "A" to the Allotment Order No. 134 of 10/2023

Construction of Water Supply Scheme Lower Nambla by way of Construction/ Commissioning and Testing of Intake Chambers /SSFPs/ Protection works, Chain Link fencing, and other allied works (for providing 100% FHTC)

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5Mtr in width, as well as 10m on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils	406.710	Cum	585.195	238004.56
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	81.220	Cum	215.590	17510.18
3	Providing and laying stone soling 2nd class	36.940	Cum	668.794	24705.25
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work up to plinth level with. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size)	24.850	Cum	5275.096	131086.15
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring, and shuttering(all work upto plinth level) with . 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	87.250	Cum	7014.737	612035.77
6	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level with 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	28.970	Cum	8463.825	245197.00
7	Reinforced Cement concrete work in walls (any Thickness) including attached pillasters buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement with 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	49.880	Cum	10207.826	509166.38
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level including curing excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	3.950	Cum	10686.539	42211.83
9	Providing hoisting and fixing upto floor five level pre cast reinforced cement concrete work in string courses, bends, coopings, bedplates, anchor block, plain window sills, and the like including setting in position in cement mortar 1:5:3 including cost of centering shuttering and curring but excluding cost of reinforcement 1:1.5:3 1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	0.710	Cum	9804.483	6961.18

	Particulars	Qty	Unit	Rate	Amount
	Centering and shuttering including strutting propping etc. and removal of Form ~~for. Work for.~~			0.000	0.00
	Foundations, footings, bases of columns etc.	24.290	Sqm	284.596	6912.82
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	848.040	Sqm	622.627	528012.81
10.3	Suspended floors, roofs, landings, balconies and access platform.	28.215	Sqm	689.626	19457.80
10.4	Columns, Pilers, abutment, posts and struts.	25.200	Sqm	737.963	18596.66
11	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	563.270	Sqm	388.430	218790.97
12	Providing and mixing water proofing materials in cement concrete work in doses by weight of cement as per manufacturer specification	570.000	Kg	73.400	41838.14
13	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron ~~embedded~~ into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements - handles/hinges Complete Job.	1090.000	Kg	110.822	120795.87
14	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	4539.080	Kg	110.822	503029.47
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete abve plinth level TMT Bars.	8123.140	Kg	94.585	768326.18
16	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	268.590	Kg	110.822	29765.65
17	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railling and similar works and applying primer coat	78.330	Kg	206.356	16163.88
18	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
18.1	65mm dia	5.000	Nos	5425.000	27125.00
18.2	50mm dia	4.000	Nos	3797.500	15190.00
19	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia length	50.000	No	217.000	10850.00
20	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	59.690	Cum	9222.500	550491.03
21	Providing and Fixing of 4-mm dia thick GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	312.200	Sqm	795.848	248463.59
22	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
22.1	Cement and Steel (55Kms)	115.350	Mton	723.435	83448.18

	Particulars	Qty	Unit	Rate	Amount
	Sand. (60 kms)	98.560	Cum	867.707	85521.21
3	Agg. 20mm (80Kms)	153.180	Cum	1083.318	165942.69
4	Agg. 40mm (80Kms	22.351	Cum	1175.272	26268.50
	Stone Soling (07-Kms)	36.940	Cum	301.305	11130.19
2.6	Chain Link Fencing (55Kms)	0.340	Mton	723.435	245.97
23	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
23.1	Cement (1000 mtrs)	70.630	Mton	499.599	35286.68
23.2	Steel (1000 mtrs)	15.380	Mton	1073.217	16506.08
23.3	Sand. (1000 mtrs)	98.560	Cum	1169.869	115302.26
23.4	Agg. 20mm (1000 mtrs)	153.180	Cum	1169.869	179200.49
23.5	Agg. 40mm (1000 mtrs)	22.351	Cum	1264.665	28266.53
23.6	Stone Soling (500 mtrs)	36.940	Cum	792.918	29290.39
23.7	Chain Link Fencing (1000 mtrs)	0.340	Mton	1073.217	364.89
				Total	5727462.23

Rupees Fifty Seven Lakh(s) Twenty Seven Thousand Four Hundred Sixty Two And Paise Twenty Three Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri