Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 30 of 08/2024

M/S	:	**AIJAZ AHMAD AWAN**
S/O	:	**Abdul Latief Awan**
R/O	:	**Sultan Dhaki Uri**
Registration No.	:	**SE-R&B-SB/BEE 189 of 2019-20**
TIN No./GST No:-	:	**01AKCPA1123A1ZO**
Name of work	:	***Construction of Water Supply Scheme Jhulla Chidi Maidanan by way of construction of Pump House/ (for providing 100% FHTC) under JJM***
eNIT No.	:	**34 /Hyd/Uri of 2023-24** TENDER ID 2023_IFC_226607_2
Your Tender Received in response to	:	eNIT No:34/Hyd/Uri_of_2023-24 Dated: 16/08/2023 issued under endorsement No:- HDU/CC-02/3563-73 Dated: 17/08/2023 (S. No: 02) Tender ID : 2023_IFC_226607_2
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/eNIT-16/3894-96 Dated:- 02/09/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/8482-95 Dated:- 31/10/2023***
Ref: to AAA	:	**Accorded by Chief Engineer vide Order No. CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022 endorsed vide No: CE/PHE/DB/18266-74 Dated:- 31/08/2022.**
Ref: to Tech. Sanction	:	**Granted vide Order issued under No. CE/PHE/DB/191 of 08/2022 Dated:- 31/08/2022 endorsed vide No: CE/PHE/DB/18841-45 Dated:- 31/08/2022.**
LOI Issued under No:-	:	**NIT NO. 34/5305-06 Dated:-31/10/2023**
Advertisement cost	:	**Rs: 45.34Lacs**
Allotted cost	:	**₹ 4928500.62** **Rupees Forty Nine Lakh(s) Twenty Eight Thousand Five Hundred And Paise Sixty Two Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	
Name of the Bank	:	

Bid Security Declaration Format

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN.

Scanned with OKEN Scanner

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri
(Syed Shalat

NO: HDU/CC-04/ 1806-18

DATED: 14-8-2024

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**

2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**

3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**

4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/8482-95 Dated:- 31/10/2023**

5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**

6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**

7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**

8 **Chief Planning Officer Baramulla(Member DJJM) for information.**

9 **Chief Medical Officer Baramulla(Member DJJM) for information.**

10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.**

11 **District Information Officer Baramulla (Member DJJM) for information.**

12 **Assistant Executive Engineer PHE Sub Division Uri for information.**

13 **File.**

Scanned with OKEN Scanner

Annexure "A" to the Allotment Order No. 30 of 08 /2024

Construction of Water Supply Scheme Jhulla Chidi Maidanan by way of construction of Pump House/ (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5m in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils	797.470	Cum	585.893	467232.09
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	55.250	Cum	215.987	11933.28
3	Providing and laying stone soling 2nd class	29.710	Cum	670.027	19906.50
4	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	15.040	Cum	5284.815	79483.61
5	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 3 : 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40-mm nominal size) crushed.	13.380	Cum	5910.823	79086.82
6	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding the cost of centering, shuttering, finishing and reinforcement. All works upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	4.280	Cum	7585.825	32467.33
7	Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	2.560	Cum	7027.662	17990.81
8	Providing and laying in position specified grade of reinforced cement concrete including cuirring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	24.200	Cum	8479.426	205202.11
9	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	43.540	Cum	10226.643	445268.03
10	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	12.020	Cum	10706.238	128688.98
11	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
11.1	Foundations, footings, bases of columns	18.660	Sqm	285.120	5320.34

Scanned with OKEN Scanner

Scanned with OKEN Scanner

#	Particulars	Qty	Unit	Rate	Amount
11.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	450.750	Sqm	623.775	281166.56
11.3	Suspended floors, roofs, landings, balconies and access platform.	194.230	Sqm	690.897	134192.96
11.4	Lintel Beams	5.110	Sqm	546.598	2793.12
11.5	Edges of Slab (under 20-Cm wide)	69.340	RM	263.380	18262.78
12	Columns, Pilers, abutment, posts and struts.	46.920	Sqm	739.323	34689.04
13	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	765.830	Sqm	389.146	298019.68
14	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1850.000	Kg	111.026	205398.43
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	9754.000	Kg	94.754	924228.47
16	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.50 mmthick with 20mm nominal size stone aggregate. Crushed	22.290	Sqm	552.239	12309.42
17	Providing and lying 50mmthick DPC with cement concrete 1: 2: 4 and curing complete	16.250	Sqm	445.822	7244.61
18	Providing woodwork in frames of doors, windows, celestory, windows and other frames, wrought frames and fixed in position with hold fast lugs with dash fastness of required dia and length (hold fast lugs or with dash fastness shall be paid for separately Second Class Kail Wood	3.105	Cum	100075.035	310732.99
19	Brick work with common burnt clay F.P.S.(non-modualar) bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement:6 coarse sand)	34.990	Cum	8160.544	285537.43
20	Providing and fixing 35mm panelled or pannelled glazed shutter for doors, windows ad celestory widows including ISI Marked, M.S Pressed, but hinges, bright finished of required size with necessary screws excl. pannelling which will be paid for separately all complete.	5.030	Sqm	3362.961	16915.69
21	Providing and fixing paneling or panelig & glazing in pannelled & glazed shutter for doors, windows & clear stove windows. (Area of opening for pannel inserts excluding position inside groves or rebates to be measured). Pannelling for pannelled or panelled glazed shutters Decorative ply wood both sides decorative vaneer and ommericla vane or other type conformig to IS 1328 BWR Tp. (Including all sorts of carriages upto site of work)	5.060	Sqm	2099.214	10622.02
22	Providing and fixing glazed shutters for doors, windows and celestory windows using 10Kg/Sqm (4mm Thick) float glass panes including ISI Marked M.S Pressed but hinges bright finished of requuired size with necessary screws. (Including all sorts of carriages upto site of work)	15.528	Sqm	4050.216	62891.76
23	Providing and fixing 35 mm thick wire gauze shutters using galvanised M.S. wire gauze of average width for aperture 1.4 mm in both directoin with wire of dia. 0.63 mm for doors, windows and clerestory windows with hinges and necessary screws, Second class kail wood. (Including all sorts of carriages upto site of work)	20.410	Sqm	3969.344	81014.30
24	Applying Priming coat with ready mixed primer of approved brand and manufacture on wood work (hard and soft wood	42.010	Sqm	64.677	2717.06
25	Painting with synthetic enamel paint of approved brand and manufacture 2 or more coats on new works	50.390	Sqm	132.560	6679.68
26	Providing and Fixing of Rolling Shutters of approved quality	5.010	Sqm	3519.923	17634.82

Scanned with OKEN Scanner

S#	Particulars	Qty	Unit	Rate	Amount
27	Providing and fixing of Pre colour coated galvanized iron sheets (Size, shape and pitch of corrugationas approved by Engineer Incharge at site (0.5mmThick) including self driling , self tapping , Screw, EPDM seal or with Ploymer coated J ort L hooks, bolts, and nuts etc inclusing ridges/valleys of rquired width as aaproved by Engineeer Incharge at site	98.540	Sqm	902.482	88930.55
28	Providing and fixing of plained eves boarding 250X32mm nominal size (Kail wood)	17.200	RM	754.269	12973.43
29	Providing ridges or hips of width 60com overall width plain G.S Sheets fixed with Plymer coated J or L hooks, bolts and coating not less than 275 gram/m2 limpet and bitumen washers complete	8.600	RM	751.497	6462.88
30	Providing and fixing of hold fasts embebed in concrete	33.320	Kgs	121.744	4056.51
31	Supply and filling in plinth level with fine sand under floor including watering ramming consoldating and dresing complete	10.790	Cum	855.904	9235.20
32	Providing and fixing of electric wiring 3/22 for electric point through conduit (lighting)(including switch,scokets condiut wiring complete job	16.000	Point	2445.750	39132.00
33	Providing and fixing of electric wiring 7/20 for electric points (including switch,scokets condiut wiring complete job	4.000	Point	4076.250	16305.00
34	Providing and fixing of MCB mounted on wall as requried at site complete job	8.000	Point	1630.500	13044.00
35	Providing and fixing of nuts. Bolts for anchoring base of mortor the dimension of bolts be 0.45M	12.000	No	217.400	2608.80
36	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
36.1	Cement and Steel from Divisional Store (55 Kms)	57.780	Mton	724.768	41877.10
36.2	Sand. (60Kms)	88.370	Cum	869.310	76820.90
36.3	Agg. 20mm (85Kms)	89.984	Cum	1139.317	102520.33
36.4	Agg. 40mm (85Kms)	13.540	Cum	1238.310	16766.72
36.5	Stone Soling (07-Kms)	29.710	Cum	301.860	8968.26
36.6	Bricks (100Kms)	17497.000	No	3.468	60671.37
36.7	Timber (55Kms)	20.810	Cum	810.456	16865.60
37	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
37.1	Cement (500Mtrs)	48.912	Mton	306.632	14997.98
37.2	Steel (500Mtrs)	8.870	Mton	658.679	5842.48
37.3	Sand.(500Mtrs)	88.370	Cum	675.255	59672.31
37.4	Agg. 20mm (500Mtrs)	89.980	Cum	675.255	60759.47
37.5	Agg. 40mm (500Mtrs)	13.540	Cum	729.975	9883.86
37.6	Stone Soling (500Mtrs)	29.710	Cum	794.380	23601.02
37.7	Bricks (500Mtrs)	17497.000	No	1.261	22062.32
37.8	Timber (500Mtrs)	20.810	Cum	423.442	8811.83
				Total	4928500.62

Rupees Forty Nine Lakh(s) Twenty Eight Thousand Five Hundred And Paise Sixty Two Only

Checked by
Head D/Man

Executive Engineer
Hydraulic Division Uri