Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 33 of 08/2024

M/S	:	**Razia Sultan**
S/O	:	**Raja Mardan Khan**
R/O	:	**Bela Boniyar**
Registration No.	:	**1238-BK/SE-PWD/CEE/2012-13**
TIN No./GST No:-	:	**01ORUPS0156J1Z6**
Name of work	:	***Construction of Water Supply Scheme Chotali Symali by way of Construction/Commissioning and Testing of SRs /Intake Chambers Chain Link Fencing (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-B)***
eNIT No.	:	**56 /Hyd/Uri of 2023-24** TENDER ID 2024_IFC_41800_1
Your Tender Received in response to	:	eNIT No: 56/Hyd/Uri_of_2023-24 Dated: 02/01/2024 issued under endorsement No:- HDU/CC-02/6700-11 Dated: 02/01/2024 (S. No: 01) Tender ID : 2024_IFC_41800_1
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/CC-02/7018-19 Dated:- 23/01/2024*** ***(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/1450-63 Dated:- 15/06/2024***
Ref: to AAA	:	**Accorded vide Order No. 45/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/552 of 09/2022 Dated:- 10/09/2022.**
LOI Issued under No:-	:	**NIT NO. 56/737-38 Dated:- 20/06/2024**
Advertisement cost	:	**Rs: 18.97 Lacs**
Allotted cost	:	**₹ 2181017.76** **Rupees Twenty One Lakh(s) Eighty One Thousand Seventeen And Paise Seventy Six Only**
Time of completion	:	90-days
M.H. of Account	:	**(JJM)**
Ref. To CDR No.	:	
Name of the Bank	:	**BSDF**

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

Xen.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @ 2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Executive Engineer
Hydraulic Division Uri
(Syed Shafat)

Head Assistant

NO: HDU/CC-04/ 1748-60.

DATED: 14-08-2024.

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**
2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**
3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**
4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/1450-63 Dated:- 15/06/2024**
5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**
6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**
7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**
8 **Chief Planning Officer Baramulla(Member DJJM) for information.**
9 **Chief Medical Officer Baramulla(Member DJJM) for information.**
10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**
11 **District Information Officer Baramulla (Member DJJM) for information.**
12 **Assistant Executive Engineer PHE Sub Division Uri for information.**
13 **File.**

Annexure "A" to the Allotment Order No. 33 of 08/2024

Construction of Water Supply Scheme Chotali Symali by way of Construction/Commissioning and Testing of SRs /Intake Chambers Chain Link Fencing (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-B)

S#	Particulars	Qty	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge				
1.1	In all kinds of soils (Bulk)	116.190	Cum	620.253	**72067.14**
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	23.230	Cum	228.505	**5308.17**
3	Providing and laying stone soling 2nd class	15.440	Cum	708.860	**10944.80**
4	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	9.480	Cum	5591.110	**53003.73**
5	Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	34.060	Cum	7434.974	**253235.22**
6	Providing and laying in position specified grade of reinforced cement concrete including cuirring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	7.996	Cum	8970.874	**71731.11**
7	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	11.580	Cum	10819.355	**125288.13**
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15° landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	1.529	Cum	11326.747	**17318.60**
9	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement	1.060	Cum	11965.192	**12683.10**
10	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	**0.00**
10.1	Foundations, footings, bases of columns	20.290	Sqm	301.645	**6120.38**
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	282.730	Sqm	659.928	**186581.30**
10.3	Suspended floors, roofs, landings, balconies and access platform.	11.790	Sqm	730.940	**8617.78**
10.4	Arches, Domes, walls upto 60 mtr span	10.610	Sqm	2399.820	**25462.09**
11	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	136.190	Sqm	411.700	**56069.42**

	Particulars	Qty	Unit	Rate	Amount
12	Providing and fixing G.I. chain link fabric fencing of required width in mesh size 50x50 mm including strengthening with 2 mm dia wire or nuts, bolts and washers as required complete as per the direction of Engineer-in	186.280	Sqm	843.525	**157131.84**
13	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	400.000	Kg	77.740	**31096.00**
14	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete	1450.090	Kg	117.461	**170329.02**
15	Supplying at site Angle iron post & strut of required size including bottom to be split and bent at right angle in opposite direction for 10 cm length and drilling holes upto 10 mm dia. etc. complete.	730.800	Kg	123.050	**89924.94**
16	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	350.220	Kg	117.576	**41177.47**
17	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	2152.080	Kg	100.246	**215736.34**
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	255.000	Kg	117.576	**29981.88**
19	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	**0.00**
19.1	40mm dia	2.000	Nos	4025.000	**8050.00**
20	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality			0.000	**0.00**
20.1	50mm dia	6.000	Nos	575.000	**3450.00**
21	Providing and fixing of (8mm-thick) MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carraiges upto site of work complete job.			0.000	**0.00**
21.1	100mm dia	30.000	Joints	1495.000	**44850.00**
22	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	**0.00**
22.1	Cement and Steel (55-Kms)	27.660	Mton	766.774	**21208.97**
22.2	Sand. (60Kms)	32.033	Cum	919.690	**29460.41**
22.3	Agg. 20mm (80Kms)	49.800	Cum	1148.218	**57181.23**
22.4	Agg. 40mm (80Kms	8.530	Cum	1247.992	**10645.37**
22.5	Stone Soling (07-Kms)	15.440	Cum	319.355	**4930.84**
23	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	**0.00**
23.1	Cement (3000Mtrs)	22.660	Mton	1350.008	**30591.18**

S#	Particulars	Qty	Unit	Rate	Amount
23.2	Steel (3000Mtrs)	4.671	Mton	2900.070	13546.23
23.3	Sand. (3000Mtrs)	32.033	Cum	3342.130	107058.45
23.4	Agg. 20mm (3000Mtrs)	49.800	Cum	3342.199	166441.51
23.5	Agg. 40mm (3000Mtrs)	8.530	Cum	3613.013	30819.00
23.6	Stone Soling (500Mtrs)	15.440	Cum	840.422	12976.12
				/Total	2181017.76

Rupees Twenty One Lakh(s) Eighty One Thousand Seventeen And Paise Seventy Six Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri