Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 140 of 10/2023

M/S	:	Khurshid Ahmad Khan
S/O	:	Mohammad Dilawar Khan
R/O	:	Moradpora Mangnipora Bandipore
Registration No.	:	354/AYY/CE/CID/PDC/2010-11
TIN No./GST No:-	:	01BEXPK5362K1Z3
Name of work	:	*Construction of Water Supply Scheme Bandi Machikrand by way of Construction/ Commissioning and Testing of Intake Chambers Protection works, , Chain Link fencing laying and fitting of GI Pipes and other allied works (for providing 100% FHTC) under JJM*
eNIT No.	:	06/Hyd/Uri of 2023-24 TENDER ID 2023_IFC_210603_2
Your Tender Received in response to	:	eNIT No:06/Hyd/Uri_of_2023-24 Dated: 27/04/2023 issued under endorsement No:- HDU/CC-02/420-31 Dated: 27/04/2023 (S. No: 02) Tender ID : 2023_IFC_210603_02
Reference	:	*(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.* *(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.* *(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.* *(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.* *(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).* *(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.* *(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.* *(viii) This Office Letter No: HDU/eNIT-09/3128-29 Dated:- 01/08/2022 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5037-50Dated: 04/08/2023*
Ref: to AAA	:	Accorded vide Order No. 41/SE/HYD/DB/JJM of 2022-23 Dated:- 26/08/2022.
Ref: to Tech. Sanction	:	Accorded vide Order No. CE/PHE/DB/556 of 09/2022 Dated:- 10/09/2022.
LOI Issued under No:-	:	NIT NO. 06/3286-87 Dated:- 08/08/2023
Advertisement cost	:	Rs: 131.97Lacs
Allotted cost	:	₹ 13975297.77 Rupees One Crore Thirty Nine Lakh(s) Seventy Five Thousand Two Hundred Ninety Seven And Paise Seventy Seven Only
Time of completion	:	120-days
M.H. of Account	:	(JJM)
Ref. To CDR/TDR No.	:	BSDF:
Name of the Bank	:	

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of 120 days from the date of issuance of LOI from this office strictly in accordance with the approved proposals. failing which the work shall have to be got executed through any other means at your risk and cost. besides CDR if any deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after deposition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G O.)

Checked by

Head Draftsman

Executive Engineer
Hydraulic Division Uri

NO: HDU/CC-04/ 5139-51

DATED: 21-10-2023

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**

2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**

3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**

4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5037-50 Dated: 04/08/2023**

5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**

6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**

7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**

8 **Chief Planning Officer Baramulla(Member DJJM) for information.**

9 **Chief Medical Officer Baramulla(Member DJJM) for information.**

10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**

11 **District Information Officer Baramulla (Member DJJM) for information.**

12 **Assistant Executive Engineer PHE Sub Division Uri for information.**

13 **File.**

Annexure "A" to the Allotment Order No. 140 of 10/2023

Construction of Water Supply Scheme Bandi Machikrand by way of Construction/ Commissioning and Testing of Intake Chambers Protection works, , Chain Link fencing laying and fitting of GI Pipes and other allied works (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
1.1	In all kinds of soils	5554.560	Cum	571.711	3175603.05
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	4838.300	Cum	210.622	1019052.42
3	Providing and laying stone soling 2nd class incl. cost of stones	272.970	Cum	653.384	178354.23
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work up to plinth level with 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size)	37.430	Cum	5153.545	192897.19
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work up to plinth level with . 1: 3 : 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40-mm nominal size)	29.000	Cum	5764.004	167156.13
6	Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	151.420	Cum	6853.107	1037697.42
7	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding cost of centering shuttering finishing and reinforcement (all work upto plinth level with 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	21.370	Cum	8268.806	176704.38
8	Reinforced Cement concrete work in walls (any Thickness) including attached pillasters buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement with 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	30.810	Cum	9972.623	307256.52
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	2.410	Cum	10440.306	25161.14
10	Reinforced cement concrete work in arches, archribs, vaults Shells folded plates and roofs having slope more than 15^0 upto floor five level including curing but excluding cost of centering and shuttering, finshing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	2.160	Cum	11028.786	23822.18
11	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	69.680	Cum	2650.000	184652.00
12	Centering and shuttering including strutting propping etc. and removal of Form ~~for~~ Work for .			0.000	0.00

S#	Particulars	Qty	Unit	Rate	Amount
12.1	Foundations, footings, bases of columns etc.	127.060	Sqm	278.038	35327.51
12.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	759.180	Sqm	608.281	461794.77
12.3	Suspended floors, roofs, landings, balconies and access platform.	77.190	Sqm	673.736	52005.68
12.4	Lintel Beams	10.270	Sqm	533.021	5474.13
12.5	Edges of Slab (Under 20-Cm wide)	117.000	Sqm	256.838	30050.05
12.6	Arches, Domes, vaults upto 6-mtr span	21.630	Mtr	2212.008	47845.73
13	Columns, Pilers, abutment, posts and struts.	37.800	Sqm	720.959	27252.25
14	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	432.210	Sqm	379.480	164015.05
15	Providing and mixing water proofing materials in cement concrete work in doses by weight of cement as per manufacturer specification	600.000	Kg	71.667	42999.96
16	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	7088.020	Kg	108.268	767408.58
17	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete above plinth level TMT Bars.	7434.140	Kg	92.406	686955.42
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	76.740	Kg	108.268	8308.52
19	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.50 mmthick with 20mm nominal size stone aggregate. Crushed	42.360	Sqm	588.300	24920.39
20	Providing and lying 50mmthick DPC with cement concrete 1: 2: 4 and curing complete	24.000	Sqm	434.743	10433.83
21	Providing woodwork in frames of doors, windows, celestory, windows and other frames, wrought frames and fixed in position with hold fast lugs with dash fastness of required dia and length (hold fast lugs or with dash fastness shall be paid for separately Second Class Kail Wood	0.750	Cum	97589.271	73191.95
22	Brick work with common burnt clay F.P.S.(non-modualar) bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement:6 coarse sand)	22.210	Cum	7957.844	176743.72
23	Providing and fixing 35mm panelled or pannelled glazed shutter for doors, windows ~~&~~ celestory widows including ISI Marked, M.S Pressed, but hinges, bright finished of required size with necessary screws excl. pannelling which will be paid for separately all complete.	9.610	Sqm	3279.428	31515.30
24	Providing and fixing paneling or panelig & glazing in pannelled & glazed shutter for doors, windows & clear stove windows. (Area of opening for pannel inserts excluding position inside groves or rebates to be measured). Pannelling for pannelled or panelled glazed shutters Decorative ply wood both sides decorative vaneer and ommericla vane or other type conformig to IS 1328 BWR Tp. (Including all sorts of carriages upto site of work)	7.230	Sqm	2047.072	14800.33
25	Providing and fixing glazed shutters for doors, windows and celestory windows using 10Kg/Sqm (4mm Thick) float glass panes including ISI Marked M.S Pressed but hinges bright finished of requuired size with necessary screws. (Including all sorts of carriages upto site of work)	7.350	Sqm	3949.613	29029.66

S#	Particulars	Qty	Unit	Rate	Amount
26	Providing and fixing 35 mm thick wire gauze shutters using galvanised M.S. wire gauze of average width for aperture 1.4 mm in both directoin with wire of dia. 0.63 mm for doors, windows and clerestory windows with hinges and necessary screws, Second class kail wood. (Including all sorts of carriages upto site of work)	9.000	Sqm	3870.749	**34836.74**
27	Providing and laying of 1st quality ceramic glazed wall/floor tiles conforming to IS 13753 of minimum thick ness 5mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalnet nake in all colours, shades except bergundy , bottle green black of any size as approved by Engineer Incharge laid on 20mm thick bed of cement cmortar (1:4) including pointing the joints with white cement and matching pigments etc complete.	37.000	Sqm	1289.013	**47693.48**
28	Flooring with marble stone of specified thickness as per sampleof marble approved by Engineer Incharge over 20mm (average) thick base of cement mortar 1:4 (1 Cement 4: crse sand) laid and jointed with grey cement slurry including rubbing, polishing and curing complete with Udaipur Green Marble	4.180	Sqm	2338.837	**9776.34**
29	Finishing walls with water proofing cement paint (Two or more coats) Work applied @3.84Kg/10Sqm	101.000	Sqm	97.308	**9828.11**
30	Applying One coat of Cement Primer of approved brand manufacture on wall shape	101.000	Sqm	62.911	**6354.01**
31	Applying Priming coat with ready mixed primer of approved brand and manufacture on wood work (hard and soft wood	37.000	Sqm	63.070	**2333.59**
32	Painting with synthetic enamel paint of approved brand and manufacture 2 or more coats on new works	37.000	Sqm	129.267	**4782.88**
33	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railling and similar works and applying primer coat	21.000	Kg	184.705	**3878.81**
34	Providing and fixing of Pre colour coated galvanized iron sheets (Size, shape and pitch of corrugationas approved by Engineer Incharge at site (0.5mmThick) including self driling , self tapping , Screw, EPDM seal or with Ploymer coated J or L hooks, bolts, and nuts etc inclusing ridges/valleys of rquired width as aaproved by Engineeer Incharge at site	88.000	Sqm	880.065	**77445.72**
35	Providing and fixing of plained eves boarding 250X32mm nominal size (Kail wood)	37.500	RM	735.534	**27582.53**
36	Providing ridges or hips of width 60cm overall width plain G.S Sheets fixed with Plymer coated J or L hooks, bolts and coating not less than 275 gram/m2 limpet and bitumen washers complete	10.670	RM	732.831	**7819.31**
37	Providing and fixing of hold fasts embebed in concrete	38.000	Kgs	118.720	**4511.36**
38	Providing and fixing of water closet (Indian Type) squatting pan with 10mm dia PR s trap fluhing cistern with handle lower with all fittings and fixtures	1.000	No	5366.250	**5366.25**
39	Supply and filling in plinth level with fine sand under floor including watering ramming consoldating and dresing complete	18.000	Cum	834.644	**15023.59**
40	Providing and fixing of soil, waste and went pipes			0.000	**0.00**
40.1	10mmDia Pipe	20.000	M	952.802	**19056.04**
40.2	75mm dia pipe	15.000	M	818.447	**12276.71**
41	Providing and Fixing white viterous China pedestal for wash basin completely recesed at back for reception of pipes and fittings	1.000	No	1324.205	**1324.21**
42	Stainless Steel Kitchen sink with CI brackets and plug 40mm with drain board.	1.000	No	3252.218	**3252.22**
43	PVC waste pipe for sink and wash basin 40mm semi right	2.000	No	82.680	**165.36**
44	Trap for self cleaning design with hinded grating	2.000	No	819.910	**1639.82**
45	600mm long towel rail	1.000	No	318.000	**318.00**

S#	Particulars	Qty	Unit	Rate	Amount
46	Providing and fixing of 450X450 main hole cover and frame for septic tank	4.000	No	636.000	**2544.00**
47	Providing and fixing of chlorinated olyviml Chloride (CPVC) pipes having thermal stability for hot and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer incharge	36.000	No	248.199	**8935.16**
48	Providing and fixing of electric wiring 3/22 for electric point through conduit (lighting)(including switch,scokets condiut wiring complete job	20.000	Point	2385.000	**47700.00**
49	Providing and fixing of electric wiring 7/20 for electric points (including switch,scokets condiut wiring complete job	10.000	Point	3975.000	**39750.00**
50	Providing and fixing of MCB mounted on wall as requried at site complete job	4.000	Point	1590.000	**6360.00**
51	Providing and fixing of mirror of superior (approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board baking (recanguler shape 453*357mm	2.000	No	1166.000	**2332.00**
52	Providing and fixinng of 600x120mm x 5mm glass shelf with edegs round of supported on anodise aluminium angle frame with cp brass brackest and guard rail complete fixed with 40mm long screws complete job	1.000	No	901.000	**901.00**
53	Providing and fixing of bends of required degree with excee door,insertion rubber insertion etc			0.000	**0.00**
53.1	100mm dia	4.000	No	561.800	**2247.20**
53.2	75mm dia	4.000	No	371.000	**1484.00**
54	Providing and fixing double equal junction of required degree			0.000	**0.00**
54.1	100mm dia	3.000	No	848.000	**2544.00**
54.2	75mm dia	3.000	No	742.000	**2226.00**
55	Providing and fixing of floor trapes			0.000	**0.00**
55.1	100 mm dia	2.000	No	1007.000	**2014.00**
55.2	75mm dia	1.000	No	826.800	**826.80**
56	Providing and fixing of water heating gysers I.S.I Mark standard quality 50 liter capacity with inlet outlet connection and electric connection complete job	1.000	No	9010.000	**9010.00**
57	Providing and fixing of hardware items,i.e handles tower bolts locking arrangement etc as per the direction of in charge engineer complete Job	1.000	Job	31800.000	**31800.00**
58	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	**0.00**
58.1	65mm dia	4.000	Nos	5300.000	**21200.00**
58.2	50mm dia	2.000	Nos	4240.000	**8480.00**
59	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality			0.000	**0.00**
59.1	50mm dia	6.000	Nos	530.000	**3180.00**
60	Providing and fixing of 8mm-Thick MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carraiges upto site of work complete job.			0.000	**0.00**
60.1	80mm dia	127.000	Joints	1272.000	**161544.00**
60.2	65mm dia	545.000	Joints	1166.000	**635470.00**
60.3	50mm dia	337.000	Joints	1060.000	**357220.00**
60.4	40mm dia	182.000	Joints	954.000	**173628.00**
61	Laying and fitting of GI Pipes with GI fitting excluding trenching and refilling etc.			0.000	**0.00**
61.1	80 mm dia GI pipes	2000.000	Mtr	77.433	**154866.00**
61.2	65 mm dia GI pipes	6000.000	Mtr	77.433	**464598.00**

S#	Particulars	Qty	Unit	Rate	Amount
61.3	50 mm dia GI pipes	3800.000	Mtr	43.248	164342.40
61.4	40 mm dia GI pipes	2200.000	Mtr	43.248	95145.60
61.5	25 mm dia GI pipes	2500.000	Mtr	32.489	81222.50
61.6	20 mm dia GI pipes	3000.000	Mtr	21.465	64395.00
61.7	15mm dia GI pipes	1500.000	Mtr	21.465	32197.50
62	Making connection of GI distribution branch with GI main of following sizes, by P/F of tees, incld. cutting and threading the pipe etc. complete			0.000	0.00
62.1	25 to 40 mm dia nominal bore	22.000	No	706.225	15536.95
62.2	Above 40 mm nominal bore	4.000	No	1344.875	5379.50
63	Providing and Fixing of 4mmdia -Thick GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	497.520	Sqm	777.510	386826.78
64	Providing and fixing of bolts of 16mm Dia 25Cm Long fully threaded to be embed in cement concrete with bolts including all sorts of carriages Complete Job	60.000	No	212.000	12720.00
65	Providing and fixing of MS Plates for anchoring of pipe over sadlle/anchor blocks with nuts and bolts already fitted in concrete 4mm thick 200 wide and average length 50cms MS Plate complete job in all respect	94.200	Kg	108.268	10198.88
66	Dismantling of GI Pipes (External Work Including Excavation and refiling trenches after taking out the pipes manually by mechanical means including staking of pipes within 50 mtr lead as per direction of engineer incharge at site	950.000	mtrs	117.289	111424.55
67	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
67.1	Cement and Steel from Divisional Store (45kms)	246.870	Mton	613.145	151367.19
67.2	Sand. (50 kms)	132.873	Cum	742.392	98643.88
67.3	Agg. 20mm (90kms)	208.660	Cum	1163.679	242813.18
67.4	Agg. 40mm (90kms)	68.000	Cum	1264.781	86005.14
67.5	Stone Soling (07-Kms)	81.735	Cum	294.362	24059.68
67.6	Bricks (100kms)	11105.000	No	3.381	37550.45
67.7	Timber (45kms)	0.740	Cum	607.782	449.76
68	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer 1000trs			0.000	0.00
68.1	Cement	104.050	Mton	488.088	50785.51
68.2	Steel	137.451	Mton	1048.486	144115.49
68.3	Sand.	132.873	Cum	1142.910	151861.88
68.4	Agg. 20mm	194.080	Cum	1142.910	221815.98
68.5	Agg. 40mm	68.010	Cum	1235.530	84028.37
68.6	Stone Soling (500mtrs)	81.735	Cum	774.309	63288.13
68.7	Bricks	11105.000	No	2.133	23683.86
68.8	Timber	0.740	Cum	1195.839	884.92
				Total	13975297.77

Rupees One Crore Thirty Nine Lakh(s) Seventy Five Thousand Two Hundred Ninety Seven And Paise Seventy Seven Only

Checked by

Head Draftsman

Executive Engineer
Hydraulic Division Uri