Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 07 of 06/2024

M/S	:	Naveed & Co.
Prop:	:	Naveed Anjum
S/O	:	Ghulam Qadir Ganai
R/O	:	Chandanwari
Registration No.	:	CE/UEED/AAY/30/2005-06
TIN No./GST No:-	:	01AIXPG9710G1Z8
Name of work	:	*Construction of Water Supply Scheme Laddi Kassi by way of Construction/Commissioning and Testing of SRs /Intake Chamber/PST Chain Link Fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-A)*
eNIT No.	:	33 /Hyd/Uri of 2023-24 TENDER ID 2023_IFC_224670_7
Your Tender Received in response to	:	eNIT No:33/Hyd/Uri_of_2023-24 Dated: 16/08/2023 issued under endorsement No:- HDU/CC-02/3530-40 Dated: 16/08/2023 (S. No: 07) Tender ID : 2023_IFC_224670_7
Reference	:	*(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.* *(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.* *(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.* *(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.* *(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).* *(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.* *(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.* *(viii) This Office Letter No: HDU/eNIT-16/3894-96 Dated:- 02/09/2023 (viii)* *District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/8468-81 Dated:- 31/10/2023*
Ref: to AAA	:	Accorded vide Order No. 30/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.
Ref: to Tech. Sanction	:	Accorded vide Order No. CE/PHE/DB/540 of 09/2022 Dated:- 10/09/2022.
LOI Issued under No:-	:	NIT NO. 33/5297-98 Dated:- 31/10/2023
Advertisement cost	:	Rs: 48.83 Lacs
Allotted cost	:	₹ 5249926.61 Rupees Fifty Two Lakh(s) Forty Nine Thousand Nine Hundred Twenty Six And Paise Sixty One Only
Time of completion	:	120-days
M.H. of Account	:	(JJM)
Ref. To CDR/TDR No.	:	Bid Security Declaration Format
Name of the Bank	:	

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid in order in terms of standing rules and free for the capacity of the work.

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Executive Engineer
Hydraulic Division Uri
(Syed Shafat

Head Assistant
NO: HDU/CC-04/ 794-806
DATED: 20-6-2024

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**
2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**
3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**
4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/8468-81 Dated:- 31/10/2023**
5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**
6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**
7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**
8 **Chief Planning Officer Baramulla(Member DJJM) for information.**
9 **Chief Medical Officer Baramulla(Member DJJM) for information.**
10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.**
11 **District Information Officer Baramulla (Member DJJM) for information.**
12 **Assistant Executive Engineer PHE Sub Division Uri for information.**
13 **File.**

Government of Jammu and Kashmir

Annexure "A" to the Allotment Order No. 07 of 06/2024

Construction of Water Supply Scheme Laddi Kassi by way of Construction/Commissioning and Testing of SRs /Intake Chamber/PST Chain Link Fencing and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-A)

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5m in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils(bulk)	332.490	Cum	579.909	192813.98
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	82.820	Cum	213.642	17693.85
3	Providing and laying stone soling 2nd class	33.030	Cum	662.753	21890.74
4	Hand-packing stones in wire-crates; including cost of crates and stones	34.840	cum	2688.000	93649.92
5	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	22.020	Cum	5227.445	115108.34
6	Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	49.470	Cum	6951.378	343884.65
7	Providing and laying in position specified grade of reinforced cement concrete including cuirring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	35.636	Cum	8387.377	298892.57
8	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	49.423	Cum	10115.627	499944.62
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15-Degree landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	4.809	Cum	10590.016	50927.39
10	Providing and fixing upto floor five level precast cement concrete string or lacing, courses copings bed plates anchor blocks plain window sills, shelves, louvers, steps stair cases etc including hoisting and setting fr psition with cement mortar 1:3 (1 cement: 3 coarse sand) cost of required centring shuttering and curing complete l: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	0.430	Cum	9331.661	4012.61
11	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement	4.230	Cum	11186.935	47320.73

P1/3

S#	Particulars	Qty	Unit	Rate	Amount
12	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
12.1	Foundations, footings, bases of columns	26.780	Sqm	282.025	7552.63
12.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	680.790	Sqm	617.004	420049.83
12.3	Suspended floors, roofs, landings, balconies and access platform.	20.472	Sqm	683.397	13990.51
12.4	Arches, Domes, walls upto 60 mtr span	28.200	Sqm	2243.727	63273.11
12.5	Slab of clear Water Sump	14.950	Sqm	683.720	10221.61
13	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	562.480	Sqm	384.916	216507.68
14	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification.	535.000	Kg	72.684	38885.68
15	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	817.500	Kg	120.422	98445.31
16	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	998.260	Kg	109.821	109629.84
17	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	8711.990	Kg	93.731	816579.70
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	204.240	Kg	109.821	22429.83
19	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case raklling and similar works and applying primer coat	80.060	Kg	204.492	16371.65
20	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
20.1	50mm dia	6.000	Nos	4300.800	25804.80
20.2	40mm dia	2.000	Nos	3763.200	7526.40
21	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality			0.000	0.00
21.1	50mm dia	6.000	Nos	537.600	3225.60
22	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia ength	40.000	No	215.040	8601.60
23	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	43.860	Cum	9139.200	400845.31
24	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1056.800	Kg	115.046	121581.04
25	Providing and Fixing of GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	156.100	Sqm	788.659	123109.70
26	Cost for collection of boulder at dumping spot withn a radius of 100 mtr at nallah site	8.560	Cum	258.349	2211.47

P2/3

S#	Particulars	Qty	Unit	Rate	Amount
27	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
27.1	Cement and Steel (35Kms)	74.850	Mton	526.977	39444.23
27.2	Sand. 40-Kms)	87.613	Cum	646.206	56616.04
27.3	Agg. 20mm (60Kms)	132.170	Cum	1073.533	141888.91
27.4	Agg. 40mm (60Kms	55.270	Cum	1166.818	64490.02
27.5	Stone Soling (07-Kms)	66.470	cum	298.583	19846.81
28	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
28.1	Cement (2000Mtrs)	64.110	Mton	878.621	56328.40
28.2	Steel (2000Mtrs)	4.001	Mton	1832.141	7330.40
28.3	Sand. (2000Mtrs)	87.613	Cum	2142.046	187671.05
28.4	Agg. 20mm (2000Mtrs)	132.170	Cum	2142.046	283114.18
28.5	Agg. 40mm (2000Mtrs)	55.270	Cum	2315.626	127984.65
28.6	Stone Soling (500Mtrs)	66.470	Cum	785.756	52229.21
				Total	**5249926.61**

Rupees Fifty Two Lakh(s) Forty Nine Thousand Nine Hundred Twenty Six And Paise Sixty One Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri

13/3