Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 130 of 10/2023

M/S	:	**Mohammad Yousuf Awan**
S/O	:	**Ghulam Hassan Awan**
R/O	:	**Gingle Uri**
Registration No.	:	**178/A/CE/KCC/PDC/ of 1995-96**
TIN No./GST No:-	:	**01AGKPA8298G1ZF**
Name of work	:	***Construction of Water Supply Scheme Laddi Kassi by way of Construction/Commissioning and Testing of SRs /Intake Chamber/Chowkidar Quarter Chain Link Fencing/Laying and Fitting of pipes and other allied works***
eNIT No.	:	**23 /Hyd/Uri of 2023-24** TENDER ID 2023_IFC_244188_16
Your Tender Received in response to	:	eNIT No:23/Hyd/Uri_of_2023-24 Dated: 31/07/2023 issued under endorsement No:- HDU/CC-02/3061-72 Dated: 31/07/2023 (S. No: 16) Tender ID : 2023_IFC_244188_16
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/eNIT-16/3636-37 Dated:- 21/08/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5875-88 Dated: 21/08/2023***

Ref: to AAA	:	**Accorded vide Order No. 30/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/540 of 09/2022 Dated:- 10/09/2022.**
LOI Issued under No:-	:	**NIT No. 16/3683-84 Dated:- 24/08/2023**
Advertisement cost	:	**Rs: 67.00 Lacs**
Allotted cost	:	**₹ 6904954.04** **Rupees Sixty Nine Lakh(s) Four Thousand Nine Hundred Fifty Four And Paise Four Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	
Name of the Bank	:	

Bid Security Declaration Format

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

XEN

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri

NO: HDU/CC-04/ 5009-21
DATED: 21-10-2023.

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**
2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**
3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**
4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5875-88 Dated: 21/08/2023**
5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**
6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**
7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**
8 **Chief Planning Officer Baramulla(Member DJJM) for information.**
9 **Chief Medical Officer Baramulla(Member DJJM) for information.**
10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**
11 **District Information Officer Baramulla (Member DJJM) for information.**
12 **Assistant Executive Engineer PHE Sub Division Uri for information.**
13 **File.**

Annexure "A" to the Allotment Order No. 130 of 10/2023

Construction of Water Supply Scheme Laddi Kassi by way of Construction/Commissioning and Testing of SRs /Intake Chamber/Chowkidar Quarter Chain Link Fencing/Laying and Fitting of pipes and other allied works (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM (Part-B)

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5Mtr in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils	3771.380	Cum	555.833	2096255.71
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	3225.940	Cum	204.772	660583.06
3	Providing and laying stone soling 2nd class	17.230	Cum	635.237	10945.14
4	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level with. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	11.340	Cum	5010.413	56818.08
5	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level with. 1: 3 : 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40-mm nominal size) crushed.	28.900	Cum	5603.917	161953.21
6	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level) with . 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	10.840	Cum	6662.771	72224.44
7	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost of centering shuttering finishing and reinforcement (all work upto plinth level with : 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	7.156	Cum	8039.151	57528.17
8	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level including curring but excluding cost of centering shuttering, finishing and reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	10.813	Cum	9695.648	104839.04
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level including curring but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	1.449	Cum	10150.341	14707.84
10	Reinforced cement concrete work in arches, archribs, vaults Shells folded plates and roofs having slope more than 15^0 upto floor five level including curing but excluding cost of centering and shuttering, finshing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	0.860	Cum	10722.477	9221.33
11	Centering and shuttering including strutting propping etc. and removal of Form ~~for~~ Work for .			0.000	0.00

#	Particulars	Qty	Unit	Rate	Amount
11.1	Foundations, footings, bases of columns etc	14.280	Sqm	270.316	3860.11
11.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	268.700	Sqm	591.387	158905.65
11.3	Suspended floors, roofs, landings, balconies and access platform.	70.682	Sqm	655.024	46298.40
11.4	Lintel Beams	10.270	Sqm	518.217	5322.09
11.5	Edges of Slab	117.120	RM	249.705	29245.41
11.6	Arches, Domes, vaults upto 6-mtr span	8.600	Sqm	2150.573	18494.92
12	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	107.140	Sqm	368.935	39527.73
13	Providing and mixing water proofing materials in cement concrete work in doses by weight of cement as per manufacturer specification.	400.000	Kg	69.666	27866.34
14	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1589.550	Kg	105.261	167318.26
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete above plinth level TMT Bars.	2668.680	Kg	89.839	239751.72
16	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	165.870	Kg	105.261	17459.71
17	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.50 mmthick with 20mm nominal size stone aggregate. Crushed	42.360	Sqm	523.561	22178.02
18	Providing and lying 50mmthick DPC with cement concrete 1: 2: 4 and curing complete	23.720	Sqm	422.669	10025.70
19	Providing woodwork in frames of doors, windows, celestory, windows and other frames, wrought frames and fixed in position with hold fast lugs with dash fastness of required dia and length (hold fast lugs or with dash fastness shall be paid for separately Second Class Kail Wood	0.740	Cum	94878.867	70210.36
20	Brick work with common burnt clay F.P.S.(non-modualar) bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement:6 coarse sand)	22.210	Cum	7736.826	171834.91
21	Providing and fixing 35mm panelled or pannelled glazed shutter for doors, windows ad celestory widows including ISI Marked, M.S Pressed, butt hinges, bright finished of required size with necessary screws excl. pannelling which will be paid for separately all complete.	9.610	Sqm	3188.347	30640.01
22	Providing and fixing paneling or panelig & glazing in pannelled & glazed shutter for doors, windows & clear stove windows. (Area of opening for pannel inserts excluding position inside groves or rebates to be measured). Pannelling for pannelled or panelled glazed shutters Decorative ply wood both sides decorative vaneer and ommericla vane or other type conformig to IS 1328 BWR Tp. (Including all sorts of carriages upto site of work)	7.230	Sqm	1990.217	14389.27
23	Providing and fixing glazed shutters for doors, windows and celestory windows using 10Kg/Sqm (4mm Thick) float glass panes including ISI Marked M.S Pressed butt hinges bright finished of requuired size with necessary screws. (Including all sorts of carriages upto site of work)	7.350	Sqm	3839.918	28223.40

S#	Particulars	Qty	Unit	Rate	Amount
24	Providing and fixing 35 mm thick wire gauze shutters using galvanised M.S. wire gauze of average width for aperture 1.4 mm in both directoin with wire of dia. 0.63 mm for doors, windows and clerestory windows with hinges and necessary screws, Second class kail wood. (Including all sorts of carriages upto site of work)	9.010	Sqm	3763.244	33906.83
25	Providing and laying of 1st quality ceramic glazed wall/floor tiles conforming to IS 13753 of minimum thick ness 5mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalnet nake in all colours, shades except bergundy , bottle green black of any size as approved by Engineer Incharge laid on 20mm thick bed of cement mortar (1:4) including pointing the joints with white cement and matching pigments etc complete.	36.670	Sqm	1253.212	45955.30
26	Flooring with marble stone of specified thickness as per sampleof marble approved by Engineer Incharge over 20mm (average) thick base of cement mortar 1:4 (1 Cement 4: crse sand) laid and jointed with grey cement slurry including rubbing, polishing and curing complete with Udaipur Green Marble	4.180	Sqm	2273.879	9504.81
27	Finishing walls with water proofing cement paint (Two or more coats) Work applied @3.84Kg/10Sqm	101.730	Sqm	94.605	9624.21
28	Applying One coat of Cement Primer of approved brand manufacture on wall shape	101.730	Sqm	61.164	6222.19
29	Applying Priming coat with ready mixed primer of approved brand and manufacture on wood work (hard and soft wood	37.340	Sqm	61.318	2289.63
30	Painting with synthetic enamel paint of approved brand and manufacture 2 or more coats on new works	37.340	Sqm	125.677	4692.77
31	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case raklling and similar works and applying primer coat	21.000	Kg	196.002	4116.05
32	Providing and fixing of Pre colour coated galvanized iron sheets (Size, shape and pitch of corrugationas approved by Engineer Incharge at site (0.5mmThick) including self driling , self tapping , Screw, EPDM seal or with Ploymer coated J or L hooks, bolts, and nuts etc including ridges/valleys of rquired width as aaproved by Engineeer Incharge at site	88.000	Sqm	855.622	75294.77
33	Providing and fixing of plained eves boarding 250X32mm nominal size (Kail wood)	37.500	RM	715.106	26816.46
34	Providing ridges or hips of width 600mm overall width plain G.S Sheets fixed with Plymer coated J or L hooks, bolts and coating not less than 275 gram/m2 limpet and bitumen washers complete	10.670	RM	712.478	7602.14
35	Supply and filling in plinth level with fine sand under floor including watering ramming consoldating and dresing complete	17.280	Cum	811.463	14022.08
36	Finishing external/internal walls 15mm thick cement plaster with cuiring complete 1:4mix	261.220	Sqm	309.632	80882.01
37	Providing and fixing of soil, waste and went pipes			0.000	0.00
37.1	10mmDia Pipe	20.000	M	926.339	18526.79
37.2	75mm dia pipe	15.000	M	795.716	11935.74
38	Providing and Fixing white viterous China pedestal for wash basin completely recesed at back for reception of pipes and fittings	1.000	No	1287.427	1287.43
39	PVC waste pipe for sink and wash basin 40mm semi right	2.000	No	80.384	160.77
40	Trap for self cleaning design with hinded grating	2.000	No	797.138	1594.28
41	600mm long towel rail	1.000	No	309.168	309.17
42	Providing and fixing of 450X450 main hole cover and frame for septic tank	2.000	No	618.336	1236.67

Sr	Particulars	Qty	Unit	Rate	Amount
43	p f of water closet (Indian type) Squatting pan with 1mm d	1.000	no	5217.210	5217.21
44	Providing and fixing of chlorinated olyviml Chloride (CPVC) pipes having thermal stability for hot and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer incharge	36.000	No	241.306	8687.00
45	Providing and fixing of electric wiring 3/22 for electric point through conduit (lighting)(including switch,scokets condiut wiring complete job	20.000	Point	2318.760	46375.20
46	Providing and fixing of electric wiring 7/20 for electric points (including switch,scokets condiut wiring complete job	10.000	Point	3864.600	38646.00
47	Providing and fixing 12 mm thick flat pressed 3 layer medium density particle board or graded particle board (Grade I) IS: 3087 marked, in ceiling with necessary nails etc. complete (frame work to be paid separately) :	8.910	sqm	8087.217	72057.10
48	Providing and fixing of MCB mounted on wall as requried at site complete job	4.000	Point	1545.840	6183.36
49	Providing and fixing of mirror of superior (approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board baking (rectanguler shape 453*357mm	2.000	No	1133.616	2267.23
50	Providing and fixinng of 600x120mm x 5mm glass shelf with edegs round of supported on anodise aluminium angle frame with cp brass brackets and guard rail complete fixed with 40mm long screws complete job	1.000	No	875.976	875.98
51	Providing and fixing of bends of required degree with excee door,insertion rubber insertion etc			0.000	0.00
51.1	100mm dia	4.000	No	546.197	2184.79
51.2	75mm dia	4.000	No	360.696	1442.78
52	Providing and fixing double equal junction of required degree			0.000	0.00
52.1	100mm dia	3.000	No	824.448	2473.34
52.2	75mm dia	3.000	No	721.392	2164.18
53	Providing and fixing of floor trapes			0.000	0.00
53.1	100 mm dia	2.000	No	979.032	1958.06
53.2	75mm dia	1.000	No	803.837	803.84
54	Providing and fixing of water heating gysers I.S.I Mark standard quality 50 liter capacity with inlet outlet connection and electric connection complete job	1.000	No	8759.760	8759.76
55	Providing and fixing of hardware items,i.e handles tower bolts locking arrangement etc as per the direction of in charge engineer complete Job	1.000	Job	30916.800	30916.80
56	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
56.1	50mm dia	2.000	Nos	4122.240	8244.48
56.2	40mm dia	2.000	Nos	3606.960	7213.92
57	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality			0.000	0.00
57.1	50mm dia	6.000	Nos	515.280	3091.68
58	Providing and fixing of 8mm-thick MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carraiges upto site of work complete job			0.000	0.00

S#	Particulars	Qty	Unit	Rate	Amount
58.1	80mm dia	45.000	Joints	1236.672	55650.24
58.2	65mm dia	45.000	Joints	1133.616	51012.72
58.3	50mm dia	291.000	Joints	1030.560	299892.96
58.4	40mm dia	291.000	Joints	927.504	269903.66
59	Laying and fitting of GI Pipes with GI fitting excluding trenching and refilling etc.			0.000	0.00
59.1	80 mm dia GI pipes	300.000	Mtr	75.282	22584.72
59.2	65 mm dia GI pipes	300.000	Mtr	75.282	22584.72
59.3	50 mm dia GI pipes	4000.000	Mtr	42.047	168187.39
59.4	40 mm dia GI pipes	4000.000	Mtr	42.047	168187.39
59.5	25 mm dia GI pipes	3500.000	Mtr	31.587	110553.32
59.6	20 mm dia GI pipes	4000.000	Mtr	20.869	83475.36
59.7	15mm dia GI pipes	1500.000	Mtr	20.869	31303.26
60	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
60.1	Cement and Steel (35Kms)	116.600	Mton	505.098	58894.43
60.2	Sand. 40-Kms)	46.133	Cum	619.377	28573.71
60.3	Agg. 20mm (60Kms)	56.590	Cum	1028.963	58229.00
60.4	Agg. 40mm (60Kms	10.200	Cum	1118.374	11407.41
60.5	Bricks (100Kms)	11105.000	No	3.277	36393.09
60.6	Stone Soling (07-Kms)	17.230	Cum	286.187	4930.99
60.7	Timber (30Kms)	0.740	Cum	590.902	437.27
61	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
61.1	Cement (2000Mtrs)	25.700	Mton	842.143	21643.07
61.2	Steel (2000Mtrs)	90.601	Mton	1756.074	159102.08
61.3	Sand. (2000Mtrs)	46.133	Cum	2053.113	94716.24
61.4	Agg. 20mm (2000Mtrs)	56.590	Cum	2053.113	116185.64
61.5	Agg. 40mm (2000Mtrs)	10.200	Cum	2219.486	22638.76
61.6	Stone Soling (500Mtrs)	17.230	Cum	753.133	12976.49
61.7	Bricks (2000Mtrs)	11105.000	No	3.823	42458.61
61.8	Timber (2000Mtrs)	0.740	Cum	1163.028	860.64
				Total	6904954.04

Rupees Sixty Nine Lakh(s) Four Thousand Nine Hundred Fifty Four And Paise Four Only

Checked by

Head Draftsman

Executive Engineer
Hydraulic Division Uri