Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email: urihydraulic@gmail.com

Allotment Order No. 138 of 10/2023

M/S	:	**Khurshid Ahmad Khan**
S/O	:	**Mohammad Dilawar Khan**
R/O	:	**Moradpora Mangnipora Bandipore**
Registration No.	:	**354/AYY/CE/CID/PDC/2010-11**
TIN No./GST No:-	:	**01BEXPK5362K1Z3**
Name of work	:	***Retrofitting of Water Supply Scheme Bagna Khoshmarg by way of Construction/Commissioning and Testing of /PST/ Retaining walls and other allied works (for providing 100% FHTC) under JJM***
eNIT No.	:	**09/Hyd/Uri of 2023-24** TENDER ID 2023_IFC_212041_35
Your Tender Received in response to	:	eNIT No:09/Hyd/Uri_of_2023-24 Dated: 13/05/2023 issued under endorsement No:- HDU/CC-02/779-89 Dated: 13/05/2023 (S. No: 35) Tender ID : 2022_IFC_212041_35
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/eNIT-09/3128-29 Dated:- 01/08/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5037-50 Dated: 04/08/2023***
Ref: to AAA	:	**Accorded vide Order No.CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/185 of 08/2022 Dated:- 31/08/2022.**
LOI Issued under No:-	:	**NIT NO. 09/3292-93 Dated:- 08/08/2023**
Advertisement cost	:	**Rs: 33.03Lacs**
Allotted cost	:	**₹ 3458400.31** Rupees Thirty Four Lakh(s) Fifty Eight Thousand Four Hundred And Paise Thirty One Only
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	
Name of the Bank	:	

BSDF

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR if any deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri
(Syed Shafat

NO: HDU/CC-04/ 5113-25
DATED: 21-10-2023

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**
2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**
3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**
4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5037-50Dated: 04/08/2023**
5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**
6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**
7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**
8 **Chief Planning Officer Baramulla(Member DJJM) for information.**
9 **Chief Medical Officer Baramulla(Member DJJM) for information.**
10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**
11 **District Information Officer Baramulla (Member DJJM) for information.**
12 **Assistant Executive Engineer PHE Sub Division Uri for information.**
13 **File.**

Annexure "A" to the Allotment Order No. 138 of 10/2023

Retrofitting of Water Supply Scheme Bagna Khoshmarg by way of Construction/Commissioning and Testing of /PST/ Retaining walls and other allied works (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
1.1	In all kinds of soils	361.350	Cum	564.969	204151.59
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	24.580	Cum	208.138	5116.04
3	Providing and laying stone soling 2nd class incl. cost of stones	17.440	Cum	645.679	11260.64
4	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centering and shuttering. All work up to plinth level with 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	8.600	Cum	5092.772	43797.84
5	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 3 : 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40-mm nominal size) crushed.	30.380	Cum	5696.033	173045.47
6	Providing and laying in position cement concrete of specified grade including curring but excluding the cost of centring, and shuttering(all work upto plinth level with. 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	33.620	Cum	6772.297	227684.63
7	Providing and laying in position specified grade of reinforced cement concrete including curring but excluding cost of centering shuttering finishing and reinforcement (all work upto plinth level) with I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	11.270	Cum	8171.296	92090.51
8	Reinforced Cement concrete work in wall (any Thickness) including attached pilaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level including curing but excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	18.470	Cum	9855.027	182022.34
9	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	2.420	Cum	10317.194	24967.61

	Particulars	Qty	Unit	Rate	Amount
10	Centering and shuttering including strutting propping etc. and removal of Form ~~for~~ Work for .			0.000	0.00
10.1	Foundations, footings, bases of columns	121.240	Sqm	274.759	33311.81
10.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	342.830	Sqm	601.108	206077.81
10.3	Suspended floors, roofs, landings, balconies and access platform.	13.620	Sqm	665.791	9068.07
11	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	282.070	Sqm	375.005	105777.66
12	Providing and mixing water proofing materials in cement concrete work in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	100.000	Kg	70.811	7081.10
13	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron ~~embedded~~ into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	2997.50	Kg	106.992	320707.47
14	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	5902.520	Kg	106.992	631520.35
15	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete above plinth level TMT Bars.	4765.860	Kg	91.311	435173.42
16	Providing and fixing of PVC (ISI$ Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engths	40.000	No	209.500	8380.00
17	Providing and Fixing of 4mmdia GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	155.530	Sqm	768.341	119500.11
18	Providing and fixing of bolts of 16mm Dia 25Cm Long fully threaded to be embed in cement concrete with bolts including all sorts of carriages Complete Job	80.000	No	209.500	16760.00
19	Providing and fixing of MS Plates for anchoring of pipe over sadlle/anchor blocks with nuts and bolts already fitted in concrete 4mm thick 200 wide and average length 50cms MS Plate complete job in alll respect	125.600	Kg	106.992	13438.15
20	Providing and fixing M.S Tube hand rail of approved size by welding etc. to steel ladder railing, balcony railing, staircase railing and similar works, including applying priming coat of approved steel primer.	70.460	kg	199.224	14037.32
21	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00

	Particulars	Qty	Unit	Rate	Amount
.1	Cement and Steel (35Kms	41.730	Mton	513.401	21424.21
21.2	Sand (45Kms	53.420	Cum	681.598	36410.95
21.3	Agg. 20mm (90Kms)	87.780	Cum	1149.946	100942.22
21.4	Agg. 40mm (90Kms	7.703	Cum	1249.772	9627.00
21.5	Stone Soling (7Kms)	13.330	Cum	290.891	3877.57
22	Carriage of material from road dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer Assistant Executive Engineer			0.000	0.00
22.1	Cement (2300Mtrs)	30.960	Mton	930.735	28815.56
22.2	Steel (2300Mtrs)	10.730	Mton	1999.363	21453.17
22.3	Sand (2300Mtrs)	53.420	Cum	2278.354	121709.69
22.4	Agg. 20mm (2300Mtrs)	87.780	Cum	2278.354	199993.95
22.5	Agg. 40mm (2300Mtrs)	7.703	Cum	2462.903	18971.74
22.6	Stone Soling (500Mtrs)	13.330	Cum	765.513	10204.29
				Total	**3458400.31**

Rupees Thirty Four Lakh(s) Fifty Eight Thousand Four Hundred And Paise Thirty One Only

Checked by

Head [illegible]

Executive Engineer
Hydraulic Division Uri