Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 127 of 10/2023

M/	:	**MIR CONSTRUCTIONS COMPANY**
p.	:	**Mukhtyar Ahmad Mughal**
S/O	:	**Liaqat Ali Mughal Chogata**
R/O	:	**Kundi Barjala Uri**
Registration No.	:	**SHEP/CEAAY/SANITARY/003 OF 2018**
TIN No./GST No:-	:	**01AOAPM8579C2Z3**
Name of work	:	***Construction of Water Supply Scheme Limber A and B by way of Construction/Commissioning and Testing of PSTs/ SRs (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM***
eNIT No.	:	**09/Hyd/Uri of 2023-24** TENDER ID 2022_IFC_212041_10
Your Tender Received in response to	:	eNIT No:09/Hyd/Uri_of_2023-24 Dated: 13/05/2023 issued under endorsement No:- HDU/CC-02/779-89 Dated: 13/05/2023 (S. No: 10) Tender ID : 2022_IFC_212041_10
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/eNIT-09/3128-29 Dated:- 01/08/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5037.50 Dated: 04/08/2023***
Ref: to AAA	:	**Accorded vide Order No.CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/182 of 08/2022 Dated:- 31/08/2022.**
LOI Issued under No:-	:	**NIT NO. 09/3296-97 Dated:- 08/08/2023**
Advertisement cost	:	**Rs: 58.28 Lacs**
Allotted cost	:	**₹ 6177182.51** **Rupees Sixty One Lakh(s) Seventy Seven Thousand One Hundred Eighty Two And Paise Fifty One Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	**BSDF**
Name of the Bank	:	

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR if any deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Executive Engineer
Hydraulic Division Uri

Head Assistant

NO: HDU/CC-04/ 4970-82

DATED: 21-10-2023

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**

2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**

3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**

4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5037-50Dated: 04/08/2023**

5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**

6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**

7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**

8 **Chief Planning Officer Baramulla(Member DJJM) for information.**

9 **Chief Medical Officer Baramulla(Member DJJM) for information.**

10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**

11 **District Information Officer Baramulla (Member DJJM) for information.**

12 **Assistant Executive Engineer PHE Sub Division Uri for information.**

13 **File.**

Annexure "A" to the Allotment Order No. 127 **of** 10 /2023

Construction of Water Supply Scheme Limber A and B by way of Construction/Commissioning and Testing of PSTs/ SRs (for providing 100% FHTC) under JJM (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.	974.760	Cum	571.711	557281.01
1.1	In all kinds of soils				
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	124.930	Cum	210.622	26313.01
3	Providing and laying stone soling 2nd class	41.660	Cum	653.384	27219.98
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work up to plinth level with. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	27.340	Cum	5153.545	140897.92
7	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring, and shuttering (all work upto plinth level) with. 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	7.960	Cum	6853.107	54550.73
8	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding cost of centering shuttering finishing and reinforcement (all work upto plinth level with 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	63.200	Cum	8268.806	522588.51
9	Reinforced Cement concrete work in walls (any Thickness) including attached pillasters, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement with 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	77.900	Cum	9972.623	776867.34
10	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	8.500	Cum	10440.306	88742.60

	Particulars	Qty	Unit	Rate	Amount
11	Reinforced cement concrete work in arches, archribs, vaults Shells folded plates and roofs having slope more than 15^0 upto floor five level including curing but excluding cost of centering and shuttering, finshing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	17.140	Cum	11028.786	189033.39
12	Centering and shuttering including strutting propping etc. and removal of Form ~~for~~. Work for .			0.000	0.00
12.1	Foundations, footings, bases of columns etc	40.870	Sqm	278.038	11363.41
12.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	808.390	Sqm	608.281	491728.28
12.3	Suspended floors, roofs, landings, balconies and access platform.	61.200	Sqm	673.736	41232.64
12.4	Arches, Domes, Vaults upto 6-mtr span	120.480	Sqm	2212.008	266502.72
13	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	944.290	Sqm	379.480	358339.17
14	Providing and mixing water proofing materials in cement concrete work in doses by weight of cement as per manufacturer specification	950.000	Kg	71.709	68123.55
15	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron ~~embedded~~ into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1090.000	Kg	108.268	118012.56
16	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	488.640	Kg	108.268	52904.27
17	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete above plinth level TMT Bars.	16276.830	Kg	92.406	1504068.61
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	445.650	Kg	108.268	48249.81
19	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railling and similar works and applying primer coat	83.270	Kg	201.601	16787.35
20	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
20.1	100mm dia	4.000	Nos	7950.000	31800.00
20.2	80mm dia	6.000	Nos	6360.000	38160.00
20.3	65mm dia	2.000	Nos	5300.000	10600.00
21	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality			0.000	0.00
21.1	80mm dia	32.000	Nos	848.000	27136.00

S#	Particulars	Qty	Unit	Rate	Amount
22	Providing and fixing of PVC ISI$ Mark inside concrete wall for inlet and outlet of 40mm/50mm dia ength	44.000	No	212.000	9328.00
23	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
23.1	Cement and Steel (30Kms)	72.420	Mton	463.355	33556.14
23.2	Sand. (35Kms)	111.960	Cum	573.881	64251.70
23.3	Agg. 20mm (60Kms)	154.910	Cum	847.717	131319.84
23.4	Agg. 40mm (60 Kms)	27.690	Cum	921.393	25513.38
23.5	Stone Soling (07-Kms)	7.170	Cum	294.436	2111.11
24	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer (1200 mtrs)			0.000	0.00
24.1	Cement	50.740	Mton	563.719	28603.08
24.2	Steel	9.670	Mton	1210.955	11709.93
24.3	Sand.	111.960	Cum	1336.681	149654.83
24.4	Agg. 20mm	154.910	Cum	1336.681	207065.28
24.5	Agg. 40mm	27.690	Cum	1445.003	40012.12
24.6	Stone Soling (500mtr)	7.170	Cum	774.648	5554.23
				Total	6177182.51

Rupees Sixty One Lakh(s) Seventy Seven Thousand One Hundred Eighty Two And Paise Fifty One Only

Executive Engineer
Hydraulic Division Uri

Checked by

Head D/Man