Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 09 of 06/2024

M/S	:	**JAVID AHMAD MIR**
S/O	:	**Mohammad Ramzan Mir**
R/O	:	**Lachipora Boniyar**
Registration No.	:	**SE/HYD/SPR/BEE/CIVIL 336 of 2021-22**
TIN No./GST No:-	:	**01BEDPM8932D3ZS**
Name of work	:	***Retrofitting of Water Supply Scheme Dudran Bagh Dudran by way of Construction/Testing/Commissioning of SRs/ PSTs/ Chowkidar Quarter other allied works (for providing 100% FHTC) under JJM***
eNIT No.	:	**23 /Hyd/Uri of 2023-24** TENDER ID 2023_IFC_244188_3
Your Tender Received in response to	:	eNIT No:23/Hyd/Uri_of_2023-24 Dated: 31/07/2023 issued under endorsement No:- HDU/CC-02/3061-72 Dated: 31/07/2023 (S. No: 03) Tender ID : 2023_IFC_244188_3
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/eNIT-23/3655-57 Dated:- 22/08/2023 (viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/8440-53 Dated:- 31/10/2023***
Ref: to AAA	:	**Accorded vide Order No. 47/SE/HYD/DB/JJM of 2022-23 Dated:- 26/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/531 of 09/2022 Dated:- 10/09/2022.**
LOI Issued under No:-	:	**NIT No. 23/5301-02 Dated:- 31/10/2023**
Advertisement cost	:	**Rs: 48.78 Lacs**
Allotted cost	:	**₹ 5360695.34** **Rupees Fifty Three Lakh(s) Sixty Thousand Six Hundred Ninety Five And Paise Thirty Four Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	**Bid Security Declaration Format**
Name of the Bank	:	

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

XEN

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri

NO: HDU/CC-04/ 869-81
DATED: 28-06-2024.

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**
2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**
3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**
4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/8440-53 Dated:- 31/10/2023**
5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**
6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**
7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**
8 **Chief Planning Officer Baramulla(Member DJJM) for information.**
9 **Chief Medical Officer Baramulla(Member DJJM) for information.**
10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information.**
11 **District Information Officer Baramulla (Member DJJM) for information.**
12 **Assistant Executive Engineer PHE Sub Division Uri for information.**
13 **File.**

Annexure "A" to the Allotment Order No. 09 of 06/2024

Retrofitting of Water Supply Scheme Dudran Bagh Dudran by way of Construction/Testing/Commissioning of SRs/ PSTs/ Chowkidar Quarter other allied works (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1	E/W in bulk excavation by manual means over areas (exceeding 30-cm in depth, 1.5Mtr in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils	811.420	Cum	592.746	**480965.68**
2	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	40.940	Cum	218.371	**8940.12**
3	Providing and laying stone soling 2nd class	25.020	Cum	677.424	**16949.14**
4	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed	16.640	Cum	5343.157	**88910.13**
5	Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	10.960	Cum	7105.249	**77873.53**
6	Providing and laying in position specified grade of reinforced cement concrete including cuirring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	25.650	Cum	8573.035	**219898.35**
7	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	32.270	Cum	10339.540	**333656.97**
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	2.800	Cum	10824.430	**30308.40**
9	providing and laying in position 1:3:6 mix plam cement conctere excluding cost of shuttering. Foundation Below ground level	28.900	Cum	5976.076	**172708.60**
10	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	1811.250	Kg	112.252	**203316.18**
11	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case raklling and similar works and applying primer coat	58.940	Kg	209.019	**12319.57**
12	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level inclding curing but excluding cost of centering and shuttering, finshing and reinforcement	4.170	Cum	11434.562	**47682.12**

	Particulars	Qty	Unit	Rate	Amount
3	Centering and shuttering including strutting propping etc. and removal of Form work for.			0.000	0.00
13.1	Foundations, footings, bases of columns	14.780	Sqm	288.268	4260.60
13.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc.	439.080	Sqm	630.661	276910.70
13.3	Suspended floors, roofs, landings, balconies and access platform.	73.000	Sqm	698.524	50992.28
13.4	Arches, Domes, walls upto 60 mtr span	49.040	Sqm	2293.393	112468.00
13.5	Lintels	10.270	sqm	552.632	5675.53
13.6	Edges of slab under 20 cm wide	117.180	Mtr	266.288	31203.59
14	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	330.670	Sqm	393.442	130099.47
15	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification including all sorts of carriages upto site of work complete	250.000	Kg	74.347	18586.84
16	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	6467.250	Kg	95.805	619596.99
17	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	545.000	Kg	112.252	61177.26
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	89.130	Kg	112.252	10005.01
19	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia ength	25.000	No	219.800	5495.00
20	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	0.00
20.1	65mm dia	4.000	Nos	5495.000	21980.00
21	Providing and fixing 50mmDia GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality	6.000	No	549.500	3297.00
22	Cement concrete flooring 1;2:4 (1 cement 2 course sand 4 graded stone agg) floating coat of neat cement inclding cenment slurry and curing complete, but excluding the cost of noising of steps	42.360	Sqm	610.495	25860.55
23	providing and laying 50mm thick DPC with cement conctete 1:2:4 and curinfg complete for walls	23.720	Sqm	450.744	10691.64
24	Providing wood work in frames of doors,windows,cclerestory windosand other frames,wrought framed and fixed in position with hold fasts lugsor with dash fasteners of requred dia or length(hold fast lugs or with dash fasteners shall be paid for seperatly) in 2nd class kail wood.	0.740	Cum	101179.820	74873.07
25	Brik work with common burnt clay F.P.S(non-modular)bricks of class designation 75 in foundation ,super structure,above plinth level upto floor five level uptofloor five level (1:6)mix Ground floor walls Qty=146'*9*9"=985.5	22.210	Cum	8250.633	183246.55
26	Finshing external /internal walls 15mm thick cement plasdter with curing (1:4)mix complete.	261.210	Sqm	330.195	86250.12

	Particulars	Qty	Unit	Rate	Amount
27	Providing and fixing glazed shutters for doors,windows and clerestory windows using 4mmthick float glass panes including ISI marked M.S.pressed but hinges bright finshed of requred size wit5h necessary screws class kail wood @35mm thick	7.350	Sqm	4094.929	30097.73
28	Providing and fixing wire gauze Shutters using gallvanized M.S. wire gauze of average width for aperture 1.4mm in both directions with wire of dia.0.63mm for doors,windows and slerestory windows with ISI marked M.S. pressed butthinges bright finished of requred size with necessary screws as per direction of engineer- in-charge	9.010	Sqm	4013.163	36158.60
29	providing and fixing panneled or panneled and Glazed shutters for doors andf windows and clerestory windows a fixing wityh butt hings of required sizw with necessry secures , excluding panneling which will be paid for seprately all complete as per direction of enginer incharge. (first Class kail wood)	9.610	Sqm	3400.086	32674.83
30	Providing and fixing panelling or panelling and glazing in planned or palelledand glazed shutters for doors,windows and clerestory windows(area of opening for pannel insert exculinding portion iside grooves or rebates to be measured)panelling for panelled or panelled and glazed shuters 25m to 40mm thick .	7.230	Sqm	2122.389	15344.87
31	Providing and laying first quality ceramic glazed wall/floor tilles confirming to IS 13753 of minimum thick 5mm of approvede make like,NITCO, ORIENT,SOMANY,KAJARIA or equivalent make in all colours,shades,except bergundy,bottelgreen,black of any size as approved by engineer-in-charge laid on 20mm thick bed of cement morter(1:4)including pointing the joints with white cement and matching pigmennts etc complete.	36.670	Sqm	1336.439	49007.22
32	Flooring with marble stone of specified thickness as per samole of marbale approved by engineer-in-charge,over 20mm(average)thick base of cement mortar 1:4(1 cement :4 coarse sand)laid and jointed with grey cement slurry including rubbing,polishing n=and curing complete with udaipur green marbale.	4.180	Sqm	2424.889	10136.03
33	Finishing walls with water proofing cement paint of required shade on new work (two or more coats applied @ 3.84 kg /10sqm)As per plastering inner walls washout for super structure	101.730	Sqm	100.888	10263.36
34	Applying one coat of water thinable cement primer approved brand and manufacture on wall surface.Qty as above item no 19=101.73sm	101.730	sqm	65.226	6635.41
35	Applying priming coat :with ready mixed pink or grey primer of approved brand and manufacture on wood work(hard and soft wood) with ready mixed aluminum primer of approved brand and manufacture on resinous wood and ply wood	37.340	sqm	65.391	2441.68
36	Painting with enamel paint of approved brand and manufacture to give an even shade.Two or more coats on new work	37.340	sqm	134.023	5004.42
37	Providing and applying white cement based puttey of average thickness 2mm of approved brand and manufactures,over the plasterd wall surface to prepare the surface even and smooth complete.For plinth outside	89.550	Sqm	189.468	16966.82

	Particulars	Qty	Unit	Rate	Amount
38	providing and fixing of pre colour coated glavanized iron sheets (size,shape and pitch of corrugation as approved by engineer incharge (0.5mm thick)including self drilling,self typing,screws, EPDM seal or with polymer coated J or L hooks,bolds and nuts etc including ridges/valleys of requried width as approve engineer incharges	88.000	Sqm	912.445	80295.14
39	Providing & fixing plained eves barding 250*32mm nomial size of kail wood	37.500	RM	762.596	28597.35
40	Providing ridgs or hips of width 60cm over all width plain G.S.sheets fixed with polymer coated J.or L hooks,bolts and nuts 8mm dia G.I.0.63 mm thick with zinc coating not less than 275gram/m2 limpet and bitumen washers complete	10.670	RM	759.794	8107.00
41	Supply and filling in plinth level with fine Sand under floors including watering,raming,conseladating and dressing complete	17.280	Cum	865.353	14953.29
42	providing and fixing 12mm thick flat preseed 3 layer medium density paticle board or graded paricle board (Grade1) IS:3087 marked,in celling with necessary nails etc.complete(frame work to be paid seperately)	8.910	Sqm	967.889	8623.89
43	Providing/fitting of hold fast for doors,windows of M.S plate iron 50 x 4mm including fitting of one limb with the frame and other limb in the brick work to hold the frame properly in position.	38.080	Kg	123.088	4687.19
44	Providing and fixing of water closet (Indian Type)squatting pan with 100mm dia.PR trap flushing cisten with handle lower with all fitting and fixtures.	1.000	No	5563.688	5563.69
45	Providing and fixing soil,waste and went pipes.			0.000	0.00
45.1	100mm dia pipe	20.000	MTR	987.858	19757.16
45.2	75mm dia pipe	15.000	MTR	848.560	12728.40
46	Vitres china wash basin flate back 550*400	1.000	No	1372.926	1372.93
47	Stainless steel kitchen sink with C.I.brackets and plug40mm with drain board	1.000	No	3371.875	3371.87
48	P.V.C waste pipe for sink and wash basin 40mm semiright	2.000	No	85.722	171.44
49	Trap for self cleaning design with hindede grating	2.000	No	850.077	1700.15
50	600mm long towel rail	1.000	No	329.700	329.70
51	450*450 main hole cover and frame for septic tank	2.000	No	659.400	1318.80
52	Providing and fixing Chlorinated Polyviyl Chloride (CPVC)pipes having thermal stabality for hot and cold water supply,including or CPVC plain and brass threaded fittings.This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of engineer incharge	36.000	mtr	257.331	9263.91
53	Providing and fixing of electric wiring 3/22 for electric point through conduit (lighting)(including switch,scokets condiut wiring complete job	20.000	point	2472.750	49455.00
54	Providing and fixing of electric wiring 7/20 for electric points (including switch,scokets condiut wiring complete job	10.000	point	4121.250	41212.50
55	Providing and fixing of MCB mounted on wall as requried at site complete job	4.000	point	1648.500	6594.00
56	Providing and fixing of mirror of superior (approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board baking (recanguler shape 453*357mm	2.000	NO	1208.900	2417.80
57	Providing and fixinng of 600x120mm x 5mm glass shelf with edegs round of supported on anodise aluminium angle frame with cp brass brackest and guard rail complete fixed with 40mm long screws complete job	1.000	NO	934.150	934.15
58	Providing and fixing of bends of required degree with excee door,insertion rubber insertion etc			0.000	0.00

	Particulars	Qty	Unit	Rate	Amount
58.1	100mm dia	4.000	NO	582.470	2329.88
58.2	75mm dia	4.000	NO	384.650	1538.60
59	Providing and fixing double equal junction of required degree			0.000	0.00
59.1	100mm dia	3.000	NO	879.200	2637.60
59.2	75mm dia	3.000	NO	769.300	2307.90
60	Providing and fixing of floor trapes			0.000	0.00
60.1	100 mm dia	2.000	NO	1044.050	2088.10
60.2	75mm dia	1.000	NO	857.220	857.22
61	Providing and fixing of water heatin gysers I.S.I Mark standard quality 50 liter capacity with inlet outlet connection and electric connection complete job	1.000	NO	9341.500	9341.50
62	Providing and fixing of main hole covers with frame 450x450mm size	2.000	NO	659.400	1318.80
63	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2012 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	0.00
63.1	Cement and Steel (40-Kms)	82.120	Mton	587.174	48218.71
63.2	Bricks 100-km	11105.000	Nos	3.473	38565.89
63.3	Sand. (45-Kms)	76.370	Cum	715.108	54612.82
63.4	Agg. 20mm (70-Kms)	101.730	Cum	988.100	100519.40
63.5	Stone Soling (7 Km)	25.020	Cum	305.269	7637.84
63.6	Agg. 40mm (70-Kms)	15.485	Cum	1073.965	16630.34
63.7	carriage of timber 80 km	0.740	cum	1254.487	928.32
64	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2012 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer (4000-Mtrs)			0.000	0.00
64.1	Cement	48.990	Mton	1682.184	82410.21
64.2	Bricks	11105.000	Nos	7.814	86773.25
64.3	Steel	33.130	Mton	3613.754	119723.66
64.4	Sand.	76.370	Cum	4198.488	320638.51
64.5	Agg. 20mm	101.730	Cum	4198.488	427112.16
64.6	Agg. 40mm	15.485	Cum	4538.650	70281.00
64.7	Stone Soling (500Mtrs)	25.020	Cum	803.149	20094.79
64.8	carriage of timber	0.740	cum	2356.102	1743.52
				Total	5360695.34

Rupees Fifty Three Lakh(s) Sixty Thousand Six Hundred Ninety Five And Paise Thirty Four Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri