Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 26 of 08/2024

M/S	:	**Shafi & Co.**
Prop:	:	**Nazir Ahmad Check**
S/O	:	**Late Mohammad Shafi Check**
R/O	:	**Uranbowa**
Registration No.	:	**12/SE/Hyd/AAY/Hand/2003-04**
TIN No./GST	:	**01ABFFS5250C2ZQ**

Name of work : ***Construction of Water Supply Scheme Gowalta Uroosa by way of Construction PST, Chowkidar Quarter, Intake Chambers, and other allied works (for providing 100% FHTC) under JJM***

eNIT No. : **60 /Hyd/Uri of 2023-24** TENDER ID 2024_IFC_246811_2

Your Tender Received in response to : eNIT No:60/Hyd/Uri_of_2023-24 Dated: 09/03/2024 issued under endorsement No:- HDU/eNIT-60/7622-32 Dated: 09/03/2024 (S. No: 02 Tender ID : 2024_IFC_246811_2

Reference :

(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.

(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.

(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.

(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.

(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).

(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.

(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022. (viii) This Office Letter No: HDU//NIT-60/429-30 Dated:- 21/05/2024

(ix) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/1276-89 Dated:- 06/06/2024

Ref: to AAA	:	**Accorded vide Order No.CE/PHE/DB/240 of 08/2022 Dated:- 31/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No.CE/PHE/DB/207 of 08/2022 Dated:- 31/08/2022**
Letter of Intent No:-	:	**637-38 Dated:- 10/06/2024**
Advertisement cost	:	**Rs:64.67Lacs**
Allotted cost	:	**₹ 6725935.14** **Rupees Sixty Seven Lakh(s) Twenty Five Thousand Nine Hundred Thirty Five And Paise Fourteen Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR No.	:	
Name of the Bank	:	**BSDF**

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN.

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri
(Syed Shafat

NO: HDU/CC-04/ 1683-95
DATED: 14-08-2024

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**
2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**
3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**
4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/1276-89 Dated:- 06/06/2024**
5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**
6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**
7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**
8 **Chief Planning Officer Baramulla(Member DJJM) for information.**
9 **Chief Medical Officer Baramulla(Member DJJM) for information.**
10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**
11 **District Information Officer Baramulla (Member DJJM) for information.**
12 **Assistant Executive Engineer PHE Sub Division Uri for information.**
13 **File.**

Annexure "A" to the Allotment Order No. 26 of 08/2024

struction of Water Supply Scheme Gowalta Uroosa by way of Construction PST, Chowkidar Quarter, Intake Chambers, and other allied works (for providing 100% FHTC) under JJM

#	Particulars	Qty	Unit	Rate	Amount
1.00	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 m2 on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
1.10	In all kinds of soils	629.170	Cum	539.350	**339342.84**
2.00	Filling available excavated earth excluding rock in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	51.850	Cum	198.700	**10302.60**
3.00	Providing and laying stone soling 2nd class	42.860	Cum	616.400	**26418.90**
4.00	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size) crushed.	26.390	Cum	4861.840	**128303.96**
5.00	Providing and laying in position cement concrete in specified grade including cuirring but excluding the cost of centering and shuttering. All work up to plinth level. 1: 3 : 6 (1 cement : 3 coarse sand : 6 graded stone aggregate 20-mm nominal size) crushed.	28.900	Cum	5437.740	**157150.69**
6.00	Providing and laying in position cement concrete of specified grade including cuirring but excluding the cost of centring, and shuttering(all work upto plinth level). 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	58.700	Cum	6465.190	**379506.65**
7.00	Providing and laying in position specified grade of reinforced cement concrete including cuirring but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size) crushed	28.180	Cum	7800.760	**219825.42**
8.00	Reinforced Cement concrete work in wall (any Thickness) including attached plaster, buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc upto floor five level excluding cost of centering shuttering, finishing an reinforcement 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	48.160	Cum	9408.140	**453096.02**
9.00	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 150 landings, balconies, staircases and spiral staircases upto floor five level excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	20.480	Cum	9849.350	**201714.69**
10.00	Reinforced cement concrete work in arches, archibs, valluts, shelves, folded plates and roofs having slope more than 150 floor five level incldng curing but excluding cost of centering and shuttering, finshing and reinforcement	2.760	cum	10404.520	**28716.48**
11.00	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	102.000	Cum	2500.000	**255000.00**
12.00	Centering and shuttering including strutting propping etc and removal of Form work for				**0.00**
12.10	Foundations, footings, bases of columns	152.510	Sqm	262.300	**40003.37**
12.20	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets etc	597.810	Sqm	573.850	**343053.27**
12.30	Suspended floors, roofs, landings, balconies and access platform.	85.480	Sqm	635.600	**54331.09**
12.40	Lintel Beams	10.270	Sqm	502.850	**5164.27**

S#	Particulars	Qty	Unit	Rate	Amount
	Edges of Slab under 20cm wide	117.180	mtr	242.300	28392.71
12.00	Arches, Domes, walls upto 60 mtr span	13.820	Sqm	2086.800	28839.58
13.00	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	512.190	Sqm	358.000	183364.02
14.00	Providing and mixing water proofing materials in cement concrete in doses by weight of cement as per manufacturer specification	850.000	Kg	67.600	57460.00
15.00	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1635.000	Kg	102.140	166998.90
16.00	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	2799.700	Kg	102.140	285961.36
17.00	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete TMT Bars.	9330.570	Kg	87.175	813392.44
18.00	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	319.350	Kg	102.140	32618.41
19.00	Cement concrete flooring 1:2:4 (1 cement: 2 coarse sand : 4 graded stone aggregate) finished with a floating coat of neat cement including cement slurry, but excluding the cost of nosing of steps etc. complete.50 mmthick with 20mm nominal size stone aggregate. Crushed	42.360	Sqm	555.500	23530.98
20.00	Finishing walls with water proofing cement paint of required shade on New work (two or more coats applied @ 3.84 kg/10sqm)	261.210	Sqm	91.800	23979.08
21.00	Providing and lying 50mmthick DPC with cement concrete 1: 2: 4 and curing complete	23.720	Sqm	410.140	9728.52
22.00	Providing woodwork in frames of doors, windows, celestory, windows and other frames, wrought frames and fixed in position with hold fast lugs with dash fastness of required dia and length (hold fast lugs or with dash fastness shall be paid for separately Second Class Kail Wood	0.740	Cum	92065.350	68128.36
23.00	Brick work with common burnt clay F.P.S.(non-modualar) bricks of class designation 75 in foundation and plinth in Cement mortar 1:6 (1 cement:6 coarse sand)	22.210	Cum	7507.400	166739.35
24.00	Providing and fixing 35mm panelled or pannelled glazed shutter for doors, windows ad celestory widows including ISI Marked, M.S Pressed, but hinges, bright finished of required size with necessary screws excl. pannelling which will be paid for separately all complete.	9.610	Sqm	3093.800	29731.42
25.00	Providing and fixing paneling or panelig & glazing in pannelled & glazed shutter for doors, windows & clear stove windows. (Area of opening for pannel inserts excluding position inside groves or rebates to be measured). Pannelling for pannelled or panelled glazed shutters Decorative ply wood both sides decorative vaneer and ommerida vane or other type conformig to IS 1328 BWR Tp. (Including all sorts of carriages upto site of work)	7.230	Sqm	1931.200	13962.58
26.00	Providing and fixing glazed shutters for doors, windows and celestory windows using 10Kg/Sqm (4mm Thick) float glass panes including ISI Marked M.S Pressed but hinges bright finished of requuired size with necessary screws (Including all sorts of carriages upto site of work)	7.350	Sqm	3726.050	27386.47
27.00	Providing and fixing 35 mm thick wire gauze shutters using galvanised M.S wire gauze of average width for aperture 1.4 mm in both directoin with wire of dia 0.63 mm for doors windows and clerestory windows with hinges and necessary screws, Second class kail wood (Including all sorts of carriages upto site of work)	9.010	Sqm	3651.650	32901.37

	Particulars	Qty	Unit	Rate	Amount
	Providing and laying of 1st quality ceramic glazed wall/floor tiles conforming to IS 13753 of minimum thick ness 5mm of approved make like NITCO, ORIENT, SOMANY, KAJARIA or equivalnet nake in all colours, shades except bergundy , bottle green black of any size as approved by Engineer Incharge laid on 20mm thick bed of cement cmortar (1:4) including pointing the joints with white cement and matching pigments etc complete.	36.670	Sqm	1216.050	**44592.55**
9.00	Flooring with marble stone of specified thickness as per sampleof marble approved by Engineer Incharge over 20mm (average) thick base of cement mortar 1:4 (1 Cement 4: crse sand) laid and jointed with grey cement slurry including rubbing, polishing and curing complete with Udaipur Green Marble	4.180	Sqm	2206.450	**9222.96**
30.00	Finishing walls with water proofing cement paint (Two or more coats) Work applied @3.84Kg/10Sqm	101.730	Sqm	91.800	**9338.81**
31.00	Applying One coat of Cement Primer of approved brand manufacture on wall shape	101.730	Sqm	59.350	**6037.68**
32.00	Applying Priming coat with ready mixed primer of approved brand and manufacture on wood work (hard and soft wood	37.340	Sqm	59.500	**2221.73**
33.00	Painting with synthetic enamel paint of approved brand and manufacture 2 or more coats on new works	37.340	Sqm	121.950	**4553.61**
34.00	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case raklling and similar works and applying primer coat	58.940	Kg	174.250	**10270.30**
35.00	Providing and fixing of Pre colour coated galvanized iron sheets (Size, shape and pitch of corrugationas approved by Engineer Incharge at site (0.5mmThick) including self driling , self tapping , Screw, EPDM seal or with Ploymer coated J ort L hooks, bolts, and nuts etc inclusing ridges/valleys of rquired width as aaproved by Engineeer Incharge at site	88.000	Sqm	830.250	**73062.00**
36.00	Providing and fixing of plained eves boarding 250X32mm nominal size (Kail wood)	37.500	RM	693.900	**26021.25**
37.00	Providing ridges or hips of width 60com overall width plain G.S Sheets fixed with Plymer coated J or L hooks, bolts and coating not less than 275 gram/m2 limpet and bitumen washers complete	10.670	RM	691.350	**7376.70**
38.00	Providing and fixing of hold fasts embebed in concrete	38.080	Kgs	112.000	**4264.96**
39.00	Providing and fixing of water closet (Indian Type) squatting pan with 10mm dia PR s trap fluhing cistern with handle lower with all fittings and fixtures	1.000	No	5062.500	**5062.50**
40.00	Supply and filling in plinth level with fine sand under floor including watering ramming consoldating and dresing complete	17.280	Cum	787.400	**13606.27**
40.10	10mmDia Pipe	20.000	M	898.870	**17977.40**
40.20	75mm dia pipe	15.000	M	772.120	**11581.80**
41.00	Providing and Fixing white viterous China pedestal for wash basin completely recesed at back for reception of pipes and fittings	1.000	No	1249.250	**1249.25**
42.00	Stainless Steel Kitchen sink with CI brackets and plug 40mm with drain board.	1.000	No	3068.130	**3068.13**
43.00	PVC waste pipe for sink and wash basin 40mm semi right	2.000	No	78.000	**156.00**
44.00	Trap for self cleaning design with hinded grating	2.000	No	773.500	**1547.00**
45.00	600mm long towel rail	1.000	No	300.000	**300.00**
46.00	Providing and fixing of 450X450 main hole cover and frame for septic tank	4.000	No	600.000	**2400.00**
47.00	Providing and fixing of chlorinated olyviml Chloride (CPVC) pipes having thermal stability for hot and brass threaded fittings. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer incharge	36.000	No	234.150	**8429.40**

	Particulars	Qty	Unit	Rate	Amount
	Providing and fixing of electric wiring 3/22 for electric point through conduit (lighting)(including switch,scokets condiut wiring complete job	20.000	Point	2250.000	45000.00
9.00	Providing and fixing of electric wiring 7/20 for electric points (including switch,scokets condiut wiring complete job	10.000	Point	3750.000	37500.00
50.00	Providing and fixing of MCB mounted on wall as requried at site complete job	4.000	Point	1500.000	6000.00
51.00	Providing and fixing of mirror of superior (approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board baking (recanguler shape 453*357mm	2.000	No	1100.000	2200.00
52.00	Providing and fixinng of 600x120mm x 5mm glass shelf with edegs round of supported on anodise aluminium angle frame with cp brass brackest and guard rail complete fixed with 40mm long screws complete job	1.000	No	850.000	850.00
53.00	Providing and fixing of bends of required degree with excee door,insertion rubber insertion etc				0.00
53.10	100mm dia	4.000	No	530.000	2120.00
53.20	75mm dia	4.000	No	350.000	1400.00
54.00	Providing and fixing double equal junction of required degree				0.00
54.10	100mm dia	3.000	No	800.000	2400.00
54.20	75mm dia	3.000	No	700.000	2100.00
55.00	Providing and fixing of floor trapes				0.00
55.10	100 mm dia	2.000	No	950.000	1900.00
55.20	75mm dia	1.000	No	780.000	780.00
56.00	Providing and fixing of water heating gysers I.S.I Mark standard quality 50 liter capacity with inlet outlet connection and electric connection complete job	1.000	No	8500.000	8500.00
57.00	Providing and fixing of hardware items,i.e handles tower bolts locking arrangement etc as per the direction of in charge engineer complete Job	1.000	Job	30000.000	30000.00
58.00	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)				0.00
58.10	50mm dia	14.000	Nos	4000.000	56000.00
59.00	Providing and fixing GI Bend in dome slab with one and provided with wire guage mesh. The bends are to be fixed in dome slab during concreting for elevation purpose quality				0.00
59.10	50mm dia	12.000	Nos	700.000	8400.00
60.00	Providing and fixing of PVC ISIS Mark inside concrete wall for inlet and outlet of 40mm/50mm dia engtth	20.000	No	200.000	4000.00
61.00	Providing and Fixing of 4mm GI chain link fabric fencing of required width in mesh size 50X50mm including strengthening with 2mm wire/nuts/bolts and washers as required as per instruction of Engineer Incharge at site.	77.760	Sqm	733.500	57036.96
62.00	Providing and fixing of bolts of 16mm Dia 25Cm Long fully threaded to be embed in cement concrete with bolts including all sorts of carriages Complete Job	60.000	No	200.000	12000.00
63.00	Providing and fixing of MS Plates for anchoring of pipe over sadlle/anchor blocks with nuts and bolts already fitted in concrete 4mm thick 200 wide and average length 50cms MS Plate complete job in alll respect	94.200	Kg	112.000	10550.40
64.00	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
64.10	Cement and Steel (70Kms)	80.561	Mton	799.240	64387.57
64.20	Sand (85Kms)	101.024	Cum	1048.130	105886.29
64.30	Agg 20mm (120Kms)	168.462	Cum	1395.890	235154.42

#	Particulars	Qty	Unit	Rate	Amount
[illegible]	Agg. 40mm (120Kms)	23.751	Cum	1517.150	36033.83
4.50	Stone Soling (7Kms)	42.860	Cum	277.771	11905.27
64.60	Bricks (140Kms)	11105.000	No	4.240	47085.20
64.70	Timber (60Kms)	0.740	Cum	1141.450	844.67
65.00	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shhall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer				0.00
65.10	Cement (2000Mtrs)	71.230	Mton	817.190	58208.44
65.20	Steel (2000Mtrs)	9.331	Mton	1755.400	16379.64
65.30	Sand (2000Mtrs)	101.024	Cum	1992.237	201263.75
65.40	Agg. 20mm (2000Mtrs)	168.462	Cum	1992.237	335616.23
65.50	Agg. 40mm (2000Mtrs)	23.751	Cum	2153.670	51151.82
65.60	Stone Soling (500Mtrs)	102.860	Cum	730.800	75170.09
65.70	Bricks (2000Mtrs)	11105.000	No	3.710	41199.55
65.80	Timber (2000Mtrs)	0.740	Cum	1128.540	835.12
				Total	6467245.32
					6725935.137
	Excess (+)	4.00%			

Rupees Sixty Seven Lakh(s) Twenty Five Thousand Nine Hundred Thirty Five And Paise Fourteen Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri