Government Jammu Kashmir (UT)
Office of the Executive Engineer Jal Shakti Department PHE Division, Shopian.
Email :-xenpheshopian@yahoo.in& xenpheshopain@gmail.com Phone /fax:- 01933- 260248/260284.

Allotment Order No 14 of 2023 dated 08/2023

Name: -	**Manzoor Ahmad Naikoo S/o Habibullah Naikoo R/o Shopian**		
Regd. No.	**75/BLE/SE/Hydl/Shopian/2003-04**		
email ID:		**Phone No.**	7006160020
GSTN:	01ALFPN0939N1ZG	**PAN**	ALFPN0939N
		Advertised Cost :	**₹ 29.83 lacs**
	Allotment Order No of 2023 dated /07/2023	**Alloted Cost :**	**₹ 29.83 lacs**

Subject:- Laying & Lifting of Delivery and Distribution Mains consisting of GMS Tubes and Ductile Iron Pipes of different Nominal Bores along with pipe fittings and control valves Execution of ancillary civil works like Conversion of SSFP into PST/Storage etc at Water Supply scheme **Killora** of Division Shopian of Kashmir Province of UT of J&K, under Jal Jeevan Mission

References:
1. This office Fresh E Nit No -44/JSDS of 2022-23 Dt -14.12.2022 (S No 04)
2. Minutes of meeting DJJM Shopian held on 03.02.2023.
3. Accord of Administrative Approval Order No -SE/Hydl/Spn/101 of 04/2020-21 DT:-27.01.2021 issued by Superintending Engineer Hydl Circle Shopian/Pulwama vide No SE/Hydl/Spn/4306-08 DT -27.01.2021
4. This office L.O.I NO - JSDS/5483-89 Dated -11.02.2023.
5. Technical sanction ORDER No -CE/PHE/DB/587 OF 09/2022 DT:-14.09.2022 issued by Chief Engineer Jal Shakti (PHE) Department Kashmir vide No CE/PHE/DB/22161-65 DT:-14.09.2022.

For & on behalf of Lt. Governor of J&K , contract for above mentioned job is here by fixed with you on your following quoted rates, terms & conditions:-

Sl.No	Description of Work / item(s)	No.of Qty	Units	Rate	Amount
1	Earth work in excavation by manual means in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed. All kinds of soil :1 meter from cutting edge.	624.45	cum	₹ 436.00	₹ 2,72,260.20
2	Earth work in excavation by mechanical means (hydraulic excavator) in trenches for foundations, drains, pipes, cables etc. (not exceeding 1.5 m in width) and for shafts, wells, cesspits and the like not exceeding 10 sqm on plan, including dressing of sides and ramming of bottoms lift upto 1.5 m, including getting out excavated earth and disposal of surplus excavated earth as directed, within a lead of 50 metres:All kinds of soil .	1457.05	cum	₹ 252.05	₹ 3,67,249.45
3	Laying in position centrifugally cast (spun) iron S&S or flanged pipes (excluding cost of pipe).150mm dia D.I pipe	1431.36	Qtl	₹ 245.55	₹ 3,51,476.45
4	Providing push-on-joints to Centrifugally (Spun) Cast Iron Pipes orDuctile Iron Pipes including testing of joints and including the cost of rubber gasket 150 mm dia pipe.	1018	each	₹ 144.70	₹ 1,47,304.60
5	Laying and fitting of G.I. pipes (all classes) complete excluding cost of pipes, fittings and Earth work.				
5.1	20 mm dia. nominal bore	2000	mtr	₹ 20.25	₹ 40,500.00
5.2	25 mm dia. nominal bore	1500	mtr	₹ 30.65	₹ 45,975.00
5.3	40 mm dia. nominal bore	900	mtr	₹ 40.80	₹ 36,720.00
5.4	50 mm dia. nominal bore	800	mtr	₹ 40.80	₹ 32,640.00
5.5	65 mm dia. nominal bore	650	mtr	₹ 73.05	₹ 47,482.50
6	Providing of FHTCs to every unconnected household including cost of 15mm to 20mm dia G.I pipe for a length of 6 to 20 mtrs with G.I fittings /specials incl. laying & fitting of pipes .earth work in excavation and refilling.The job includes providing and fixing of Water Meters. complete job.	181	No.	₹ 3,850.00	₹ 6,96,850.00
7	Manufacturing/ fabrication and fixing of M.S surface box/chambers of size (0.60x0.60x0.75m) made out of 6mm thick MS sheet using 40x40x5mm angle iron for frame including cutting, hoisting and fixing in position incl. all locking arrangements, handles hinges etc and applying priming coat of approved steel primer. The job includes providing and laying of cement concrete 1:2:4 on the base of frame to be embedded in, including all sorts of carriages involved for the completion of the job. The job is to carried out as per the directions of Site-incharge.complete job.	2	No.	₹ 11,000.00	₹ 22,000.00
8	Providing and fixing gun metal gate valve with C.I. wheel of approved quality (screwed end):65 mm nominal bore	5	each	₹ 1,568.85	₹ 7,844.25
9	Providing and fixing C.I. sluice valves (with cap) complete nuts, rubber insertions etc. (the tail pieces if required will be paid separately).				
9.1	150 mm dia. (Class I)	2	each	₹ 6,508.50	₹ 13,017.00
9.2	100 mm dia. (Class I)	3	each	₹ 4,597.85	₹ 13,793.55

Head Draftsman Technical Officer Executive Engineer

No:- JSDS/2356-60
Dt:- 01-08-2023

Allotment No:- 14 Dt:- 08/2023

10	Supplying,Installation,Commissioning and Testing of Electromagnetic Flow Meters of ISI/ reputed Make (.The item includes fabrication of M.S tail pieces,flanges ,nuts bolts,R.I cloth etc, cutting of existing supply line,welding,wiring from panel board to site of installation complete as per requirement of site incl cost of RCC protective chamber of suitable size incl cost of M.S covers,ladders etc .complete job.				
10.1	80 mm dia	2	No.	₹ 22,000.00	₹ 44,000.00
10.2	65 mm dia	3	No.	₹ 20,900.00	₹ 62,700.00
11	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50 m and lift upto 1.5 m.	1863.4	cum	₹ 198.70	₹ 3,70,257.58
12	Carriage of material from different sources to site of work by Mechanical Transport including loading, unloading, stacking complete				
12.1	150 mm dia D.I Pipes from Divl store for avg. lead of 04 km.	5600	mtr	₹ 6.91	₹ 38,696.00
12.2	Below 100mm dia G.I pipes from Divl store for avg. lead of 07 km.	15.36	M.T	₹ 209.87	₹ 3,223.60
13	De-silting of SSFP's & PST by way of removing of silt by manual means using Rope and Bucket method. The job includes washing and cleaning of walls, dewatering including all leads and lifts , carriage of silt for its disposal within 50mtrs lead incl. cost of all T&P required for the completion of the job.complete job.	129.6	cum	₹ 495.00	₹ 64,152.00
14	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	2068.19	kg	₹ 91.03	₹ 1,88,256.99
15	Providing corrugated G. S. sheet roofing including vertical/curved surface fixed with polymer coated J or L hooks, bolts and nuts 8mm diameter with bitumen and G.I limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (upto any pitch in horizontal/vertical or curved surface)excluding the cost of purlins, rafters and trusses and including cutting to size and shape wherever required.0.50 mm thick with zinc coating not less than 275 gram/m2	140.6	sqm	₹ 830.25	₹ 1,16,733.15
				Total Schedule Value	**₹ 29,83,126**
	Add Quoted/Accepted percentage	-(Minus) 0.010%			-₹ 298
				Alloted Amount	**₹ 29,82,828**

Terms & Conditions

1	The cost of work should in no case exceed beyond **Rs. 29.83 lacs/= (Rupees Twenty nine lac Eighty Three Thousand Only)**
2	**The overall payment under the contract will be restricted to DAP/DPR provision.**
3	This letter of allotment & your tender will constitue a legal contract document and the conditions laid down in the detailed NIT/Form No 25-double will hold good and binding upon you.
4	You have to attend the Divisional/Circle Office along with your enlistment card for drawl of agreement . However non-drawl of agreement will not prevent the contract from being enforced upon you.
5	Performance security deposited by you vide **Bank Guarantee for an amount of Rs.90000/- (Rupees ninety thousand Only) through The Anantnag central Co-op. Bank Ltd. B/u Shopian vide Reference No.BGNo.080 Dt:-15.05.2023 Date of Expiry 04.09.2025** as security deposit shall be released only after successful completion & expiry of DLP of the work.
6	The date of start of work shall be reckoned within one week from the date of issuance of the LOI/Contract allotment whichever is earlier.
7	The work shall have to be completed within a period of **one hundred Eighty (180)** days from the date of issuance of LOI or allotment mentioned above whichever is earlier.
8	The work be executed strictly in accordance with approved proposals & in close supervision of the Engineer I/C of both wings of Civil as well as Mechanical.
9	After testing and commissioning of work, the bidder will have to make a trial run of the work for a period of 03 months during which the bidder will have to operate and maintain the executed work to the full satisfaction of the Department.
10	The defects Liability period shall be for a period of 12 Months which shall commence after the successful completion of Trial run. The bidder shall be responsible to make good & remedy at his own expense any defect in works which is noticed during the DLP. In case any defect remains unattended by the firm at the completion of DLP, the department may extend the DLP for such time as deemed fit for getting the defect rectified subject to a maximum ceiling of 6 Months.
11	The bidder shall be responsible for the time and proper setting out of all the works and for the correctness of the positions, levels, dimensions and alignment of all parts of the works and for the provision of all necessary instruments, appliances and labour in connection therewith
12	The rates are including the Charges for Submission of progress, Geo-tagged photographs, vediographic record through the professional person before, during & after construction and progress reports in both hard and soft copies. Taking Cross-Sections/ L- Sections by Auto Level / ETS before and after execution. Preparation of work abstract of executed work, preparation of bills besides, the rates quoted/alloted are inclusive of taxes and the taxes viz. GST/Income tax/Cess etc. shall be deducted at source from running account bills.
13	All the Cement, R.C.C, Steel, plumbing and other works shall be strictly as per relevant IS Codes, CPHEEO norms/requirements/specifications and normal PWD practices.

Head Draftsman

Technical Officer

Executive Engineer

No:- JSUS/2356-60
Dt:- 01-08-2023

Allotment No:- 14 Dt:- 08/2023

14	You shall be solely responsible for carrying out the mandatory tests required or as decided by Engineer-in-charge for the quality control at your own costs. The cost of conducting all tests shall be borne by the contractor and shall be deemed to have been included in the item rates for various items of work and percentage rate tendered. Nothing extra shall be payable on this account.
15	You have to furnish the confirmatory survey, structural & functional design including geo-technical analysis, soil investigation, and quality control tests done at your level duly vetted by DIQC as per terms & conditions of the NIT. The vetting charges for the design if any are to be borne by you
16	The allotted works shall be subject to check by the third party monitoring agency (TPIQM) appointed by the Department. The agency shall check the quality of works executed by the agencies, quality of materials used for construction and quality of machinery installed in each scheme. The TPIQM's role shall be that of an assistant to the Employer's Representative for the purpose of monitoring and evaluation of the performance of the Contract during the Contract Period.
17	Any item of work not included in the BOQ but required for the completion of the work, shall be executed by the contractor, as directed by the Department. Such extra item shall be paid at J&K SSR 2020 rates with allotted appreciation/depreciation of the contractor. In case such item does not figure in J&K SSR 2020, the same shall be paid as per the current market rate analysis, to be approved by the competent authority.
18	No price escalation will be paid for completion of the work within stipulated time or extended date of completion due to any reason whatsoever
19	No extra claim towards any type of tax, freight, etc shall be entertained whatsoever.
20	No mobilisation advance shall be paid.
21	Retention money/Security deposit shall be 10% of the contract value. The Security Deposit is to be recovered at the rate of 10% of bill amount from Running Account Bills and shall be released after completion of the defect liability period.
22	In the event of allottee failing, declining, neglecting or delaying the supplies / works or in the event of any damage occurring or being caused by the allottee or in the event of any default or failure by the allottee in complying with any of the terms and conditions of the contract, the Department shall with or without prejudice to any other remedies available to it under any law for the timebeing enforce in the UT. a) Terminate the contract after 07 days' notice and/or b) Recover the amount of loss caused by damage, failure or default, as may be determined by the department and/or c) Recover the extra cost, if any, involved in allotting contract to other party, and/or d) Impose Liquidated damages on account of delay beyond the schedule completion period to the tune of 0.5% of the delayed portion of contract every week but not exceeding 10% value of the contract. and/or e) Forfeit the performance security and blacklist the firm.
23	All risks of loss or damage to physical property and of personal injury and death which arise during and in consequence of the performance of the Contract are the responsibility of the Bidder.
24	Any failure or commission to carry out the provision of the contract shall not give rise to any claim by the department or bidder one against the other if such failure of commission arises from the 'ACT OF GOD' which shall include all natural calamities such as fires, floods, earthquake, hurricane, strikes, riots, embargoes or from any political or other reasons beyond the control of the parties including war, or a state of insurgency.
25	The bidder shall in connection with the work provide and maintain at his own cost all lights, guards, fencing and watching, when and where necessary or required by the Department for the protection of the work or safety and convenience of the Public etc
26	From the commencement of the work to the completion thereof the same shall be under the bidders charge. The bidder shall be held responsible for and make good any loss or injuries by fire or other causes / theft and shall hold the Government harmless for any claims for injuries to persons or damage to property happening from any neglect, default, want of proper care and misconduct on the part of the bidder, or any of his employees, during the execution of work. The bidder shall be responsible for the compensation if any, to labour under the existing labour laws of the country.
27	In the event of the death or insanity or insolvency or imprisonment of the bidder or where the bidder being a partnership or firm becomes dissolved or being corporation goes into liquidation, voluntary or otherwise, the contract may, in the option of the Engineer-in-charge, be terminated by notice in writing posted at the site of the works.
28	The damage caused to the work during execution or prior to actual completion of work/handing over of the project before defect liability period due to any natural calamity/human interference, the same shall be got restored/made good by you at your own cost
29	No damage is caused to existing structures like roads, bridges, buildings or other public utilities as a result of construction of this work. Whereever any damage occures to any public/private infrastructure or public utility, the same shall be rectifed/made good by you at your own cost.
30	Adequate precaustions be taken for enviornment and social protection besides, all safety practices in vogue be strictly adhered to during execution of work
31	No objection certificate from the concerned regulatory authority may also be sought wherever required.
32	All other terms & conditions will remain same as laid down in the original NIT /SBD/GFR-2017/ Procurement Manual 2019/Operational guidelines for JJM.

Head Draftsman

Technical Officer

Executive Engineer

No:- 2356-60 Dt:- 01-08-2023

Copy to the :-

1 Chief Engineer, Kmr Jal Shakti (PHE) Department Srinagar for favour of information.

2 District Development Commissioner SShopian (Chairman District Jal Jeevan Mission) for information.

3 Superintending EngineerHydraulic Circle ShopianPulwam for favour of information period and strictly in accordance with JJM Guidelines.

4 Assistant Executive Engineer,PHE Sub-Division Shopian/Zainapora for information & necessary action. He will ensure the completion of work within the stipulated time period and strictly in accordance with JJM Guidelines.

5 File concerned.

NO:-