Government of Jammu and Kashmir
OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI
email :urihydraulic@gmail.com

Allotment Order No. 135 of 10/2023

M/S	:	BALOTE CONSTRUCTIONS COMPANY
Prop.	:	Mohammad Ashraf Balote
S/O	:	Qammar-ud-din Balote
R/O	:	Garkote Uri
Registration No.	:	117/AYY/CE/CID/PDC/2010-11
TIN No./GST No:-	:	01ANAPA7383B1ZS
Name of work	:	*Retrofitting of Water Supply Scheme Upper Nambla by way of Construction/Commissioning and Testing of Intake Chambers/PSTs/ SRs/SSFPs/ Protection works, Chain Link fencing, providing and laying of GI Pipes and other allied works (for providing 100% FHTC) under* TENDER ID 2023_IFC_210603_11
eNIT No.	:	06/Hyd/Uri of 2023-24
Your Tender Received in response to	:	eNIT No:06/Hyd/Uri_of_2023-24 Dated: 27/04/2023 issued under endorsement No:- HDU/CC-02/420-31 Dated: 27/04/2023 (S. No: 11) Tender ID : 2023_IFC_210603_11
Reference	:	*(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.* *(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.* *(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.* *(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.* *(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).* *(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.* *(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.* *(viii) This Office Letter No: HDU/eNIT-06/3130-31 Dated:- 31/07/2023(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5037-50Dated: 04/08/2023*
Ref: to AAA	:	**Accorded vide Order No. 41/SE/HYD/DB/JJM of 2022-23 Dated:- 26/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/556 of 09/2022 Dated:- 10/09/2022.**
LOI Issued under No:-	:	**NIT NO. 06/3286-87 Dated:- 08/08/2023**
Advertisement cost	:	**Rs: 138.26Lacs**
Allotted cost	:	**₹ 14988568.85** **Rupees One Crore Forty Nine Lacs Seventy Two Thousand Three Hundred Eighty Four and Paise Fifty Four Only)**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	
Name of the Bank	:	**BSDF:**

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN.

2 The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR if any deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Checked by

Head Draftsman

Executive Engineer
Hydraulic Division Uri

NO: HDU/CC-04/ 5074-86

DATED: 24-10-2023.

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**
2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**
3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**
4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5037-50 Dated: 04/08/2023**
5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**
6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**
7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**
8 **Chief Planning Officer Baramulla(Member DJJM) for information.**
9 **Chief Medical Officer Baramulla(Member DJJM) for information.**
10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**
11 **District Information Officer Baramulla (Member DJJM) for information.**
12 **Assistant Executive Engineer PHE Sub Division Uri for information.**
13 **File.**

Annexure "A" to the Allotment Order No. 135 of 10/2023

Retrofitting of Water Supply Scheme Upper Nambla by way of Construction/Commissioning and Testing of Intake Chambers/PSTs/ SRs/SSFPs/ Protection works, Chain Link fencing, providing and laying of GI Pipes and other allied works (for providing 100% FHTC) under JJM

S#	Particulars	Qty	Unit	Rate	Amount
1	Earth work in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including disposal of excavated earth lead upto 50 meters and lift upto 1.5 m, as directed by Engineer-in-Charge.				
1.1	In all kinds of soils	3634.208	Cum	585.19	**2126719.44**
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m.	2558.962	Cum	215.59	**551685.34**
3	Providing and laying stone soling 2nd class	73.890	Cum	668.79	**49417.19**
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work up to plinth level.with 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size)	48.220	Cum	5275.09	**254364.89**
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring, and shuttering(all work upto plinth level) with . 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	113.810	Cum	7014.73	**798346.55**
6	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding cost of centering shuttering finishing and reinforcement (all work upto plinth level with 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	70.222	Cum	8463.82	**594346.69**
7	Reinforced Cement concrete work in walls (any Thickness) including attached pillasters buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level incldluing curing but excluding cost of centering shuttering, finishing an reinforcement with 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	100.876	Cum	10207.83	**1029724.70**
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	8.818	Cum	10686.54	**94233.95**
9	Providing and fixing upto floor five level precast cement concrete string or lacing, courses copings bed plates anchor blocks plain window sills, shelves, louvers, steps stair cases etc including hoisting and setting in position with cement mortar 1:3 (1 cement: 3 coarse sand) cost of required centring shuttering and curing complete I: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	0.440	Cum	9804.48	**4313.97**
10	Reinforced cement concrete work in arches, archribs, vaults Shells folded plates and roofs having slope more than 15^0 upto floor five level including curing but excluding cost of centering and shuttering, finshing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	3.540	Cum	11288.90	39962.70

S#	Particulars	Qty	Unit	Rate	Amount
11	Hand-packing stone in wire crates; including cost of stones and crates and all sorts of carriages of material upto site of work	293.260	Cum	2712.50	**795467.75**
12	Centering and shuttering including strutting propping etc. and removal of Form for			0.00	**0.00**
12.1	Foundations, footings, bases of columns etc	144.000	Sqm	284.60	**40981.75**
12.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	1448.680	Sqm	622.63	**901987.64**
12.3	Suspended floors, roofs, landings, balconies and access platform.	67.470	Sqm	689.63	**46529.07**
12.4	Arches, Domes, Vaults upto 6-mtr span	35.450	Sqm	2264.18	**80265.11**
13	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	1166.160	Sqm	388.43	**452971.53**
14	Providing and mixing water proofing materials in cement concrete work in doses by weight of cement as per manufacturer specification	1220.000	Kg	73.35	**89482.12**
15	Providing and fixing of two M.S surface box for sluice/gate valve one for inlet and one for outlet including embedding of vertical members of iron embedded into concrete blocks with Angle Iron frames 50X50X6mm , Angle Iron Lid Frame 40X40X5mm with M S Sheet of 4mm thick for lid on sides and including locking arrangements handles/hinges Complete Job.	1907.500	Kg	110.82	**211392.77**
16	Structural steel work welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	5405.420	Kg	110.82	**599038.91**
17	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete above plinth level TMT Bars.	17682.710	Kg	94.58	**1672516.92**
18	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	459.240	Kg	110.82	**50893.85**
19	Providing and Fixing of Hand Rails of approved size by welding extra to steel ladder balcony railing stair case railling and similar works and applying primer coat	140.140	Kg	206.36	**28918.75**
20	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.00	**0.00**
20.1	65mm dia	2.000	Nos	5425.00	**10850.00**
20.2	50mm dia	14.000	Nos	4340.00	**60760.00**
20.3	40mm dia	2.000	Nos	3797.50	**7595.00**
21	Providing and fixing of PVC ISI Mark inside concrete wall for inlet and outlet of 40mm/50mm dia ength	80.000	Nos	217.00	**17360.00**
22	Providing/Shrouding and laying of filter media of required grade from ganderbal, Sind Nallah source inclusive of all sorts of carriages upto site of work complete job.	72.420	Cum	9222.50	**667893.45**
23	Providing and fixing of 8mm thick MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carraiges upto site of work complete job.			0.00	**0.00**
23.1	100mm dia	55.000	Joints	1410.50	**77577.50**
23.2	80mm dia	118.000	Joints	1302.00	**153636.00**
23.3	65mm dia	73.000	Joints	1193.50	**87125.50**
23.4	50mm dia	182.000	Joints	1085.00	**197470.00**
24	Laying and fitting of GI Pipes with GI fitting excluding trenching and refilling etc.			0.00	**0.00**
24.1	100 mm dia GI pipes	300.000	Mtr	116.85	**35056.35**
24.2	80 mm dia GI pipes	1000.000	Mtr	79.26	**79259.25**
24.3	65 mm dia GI pipes	500.000	Mtr	79.26	**39629.63**
24.4	50 mm dia GI pipes	3600.000	Mtr	44.27	**159364.80**

S#	Particulars	Qty	Unit	Rate	Amount
24.5	40 mm dia GI pipes	1300.000	Mtr	44.27	57548.40
24.6	25 mm dia GI pipes	2500.000	Mtr	33.26	83138.13
24.7	20 mm dia GI pipes	3000.000	Mtr	21.97	65913.75
24.8	15mm dia GI pipes	1500.000	Mtr	21.97	32956.88
25	Making connection of GI distribution branch with GI main of following sizes, by P/F of tees, incld. cutting and threading the pipe etc. complete			0.00	0.00
25.1	25 to 40 mm dia nominal bore	180.000	No	722.88	130118.63
25.2	Above 40 mm nominal bore	65.000	No	1376.59	89478.59
26	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.00	0.00
26.1	Cement and Steel (45Kms)	221.930	Mton	771.35	171185.31
26.2	Sand. (60Kms)	196.318	Cum	975.51	191510.69
26.3	Agg. 20mm (115Kms)	300.546	Cum	1514.54	455189.13
26.4	Agg. 40mm (115 Kms)	43.390	Cum	1646.11	71424.62
26.5	Stone Soling (07-Kms)	64.050	Cum	301.30	19298.55
27	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer (2000 mtrs)			0.00	0.00
27.1	Cement	132.930	Mton	886.65	117862.54
27.2	Steel	89.022	Mton	1904.61	169552.10
27.3	Sand.	196.350	Cum	2161.57	424424.18
27.4	Agg. 20mm	300.546	Cum	2161.57	649651.08
27.5	Agg. 40mm	43.390	Cum	2336.73	101390.80
27.6	Stone Soling (500mtr)	64.050	Cum	792.92	50786.40
				Total	14988568.85

Rupees One Crore Forty Nine Lakh(s) Eighty Eight Thousand Five Hundred Sixty Eight And Paise Eighty Five Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri