Government of Jammu and Kashmir

OFFICE OF THE EXECUTIVE ENGINEER HYDRAULIC DIVISION URI

email: urihydraulic@gmail.com

Allotment Order No. 131 of 10/2023

M/S	:	**Naveed & Co.**
Prop:	:	**Naveed Anjum**
S/O	:	**Ghulam Qadir Ganai**
R/O	:	**Chandanwari**
Registration No.	:	**CE/UEED/AAY/30/2005-06**
TIN No./GST No:-	:	**01AIXPG9710G1Z8**
Name of work	:	***Retrofitting of Water Supply Scheme Dudran Bagh Dudran by way of Construction of Intake Chambers/ Protection works, Chain Link fencing, laying and fitting of GI Pipes and other allied works (for providing 100% FHTC) under JJM***
eNIT No.	:	**16 /Hyd/Uri of 2023-24** TENDER ID 2023_IFC_219277_3
Your Tender Received in response to	:	eNIT No:16/Hyd/Uri_of_2023-24 Dated: 01/07/2023 issued under endorsement No:- HDU/CC-02/1587-99 Dated: 01/07/2023 (S. No: 03) Tender ID : 2023_IFC_219277_3
Reference	:	***(i) Constitution of District Jal Jeevan Mission, Administrative Council Decision No: 28-04-2020 Dated: 05-02-2020 issued vide Govt. order No: 501-JK (GAD) of 2020 Dated: 24-04-2020.*** ***(ii) Minutes of fourth meeting of the Apex committee of Jal Jeevan Mission J&K, meeting convened on 04-09-2021.*** ***(iii) Jal Shakti Department order No: 196 of JK (JSD) of 2021 Dated: 12-10-2021.*** ***(iv) Chief Engineer Kashmir PHE Jal Shakti Department office E-NIT No: 129 of 2021-22 Dated: 21-02-2022 issued under Endtt. No: CE/PHE/DB/41981-42033 Dated: 21-02-2022.*** ***(v) UT level committee meeting held on 28-04-2022 under the Chairmanship Development Commissioner Works PW (R&B).*** ***(vi) Chief Engineer Kashmir PHE Jal Shakti Department Srinagar's office letter No: CE/PHE/JJM/2617-59 Dated: 05-05-2022 & 4169-74 dated: 20-05-2022.*** ***(vii)Minutes of meeting of held on 23-05-2022 under the Chairpersonship of District Development Commissioner Baramulla (Chairperson District JJM Bla) authorization issued vide No: DDCB/Meeting/ 2022/1214-44 Dated: 24-05-2022.*** ***(viii) This Office Letter No: HDU/eNIT-16/3634-35 Dated:- 21/08/2023*** ***(viii) District Superintending Engineer Hyd. Circle Bla/Bpr HQ Sopore authorization No: SE/Hyd/DB/5875-88 Dated: 21/08/2023***
Ref: to AAA	:	**Accorded vide Order No. 47/SE/Hyd/DB/JJM of 2022-23 Dated:- 26/08/2022.**
Ref: to Tech. Sanction	:	**Accorded vide Order No. CE/PHE/DB/551/ of 09/2022 Dated:- 10/09/2022.**
LOI Issued under No:-	:	**NIT NO. 16/3685-86 Dated:- 24/08/2023**
Advertisement cost	:	**Rs: 60.70 Lacs**
Allotted cost	:	**₹ 6293334.81** **Rupees Sixty Two Lakh(s) Ninety Three Thousand Three Hundred Thirty Four And Paise Eighty One Only**
Time of completion	:	120-days
M.H. of Account	:	**(JJM)**
Ref. To CDR/TDR No.	:	**Bid Security Declaration Format**
Name of the Bank	:	

For and on behalf of LT. Governor of J&K UT the contract for above noted work is fixed with you on the following rates accepted/negotiated by you in writing on the comparative statement on the following terms and conditions as already laid down in the detailed Form No. 25 (double) and NIT subject to the condition that your Regd. Card is valid/in order in terms of standing rules and free for the capacity of the work

Allotted Rates as "Annexure A" Enclosed"

Terms and Conditions:-

1 Time of completion is essence of the contract.

XEN

The work shall have to be started by you at site immediately & ensure its successful completion within a period of **120** days from the date of issuance of LOI from this office strictly in accordance with the approved proposals failing which the work shall have to be got executed through any other means at your risk and cost, besides CDR deposited by you as security against this contract shall be forfeited.

3 An agreement shall have to be drawn up by you with the department within a period of 07 days from the date of issuance of allotment failure to execute such a formal deed shall not however prevent the contract from being enforced upon you.

4 The allotted work shall be subject to Check by the third party monitoring agency appointed by the Department.

5 Payment shall be released as per actual / measured work done not less than 20% of the allotted cost on a monthly basis.

6 Performance security equivalent to 03% of the value of the contract shall have to be deposited by you in shape of CDR/FDR/Bank Guarantee within one week of issuance of allotment order & Valid for a period of 03 months beyond the expiry of warranty period of the contract.

7 The firm shall be bound for satisfactory performance of work for 18 months after the successful commissioning of the works. If during warranty period any malfunctioning / defects arise , you shall have to rectify the same within a period of 10 days of receipt of intimation. In case of any failure on your part, the department may get the defects removed / repaired by any other means and cost involved thereof shall be recovered from you and shall be recommended for further punitive action as governed under the relevant clause of the contract including black listing.

8 After testing and commissioning of work you shall have to make a trial run of the works for a period of 03 months during which you have to operate and maintain the executed works to the full satisfaction of the department.

9 The defective liability period shall be for a period of 12 months and shall commence after the successful completion of trial run.

10 Pre & post Geo-tagged photographic evidence be taken during the execution of the work and shall have to be produced at the time of submission of the bill.

11 The date of start of the work shall reckon within 07 days from the date of issue of LOI. However date of start for laying and fitting of pipes will start within 02 days of issuance of pipe material by the department.

12 Earnest Money @2% if any deposited by you in shape of CDR/FDR/Bank Guarantee shall be released after depsoition of 03% performance security of the value of the contract

13 All other terms and conditions shall be applicable as laid down in Standard bid Document& PWD form No. 25/33.

14 Any rules/ terms and conditions if no stipulated in the bidding document, shall be strictly dealt in accordance with the relevant rules/ guidelines stipulated in General Financial Rules (GFR-2017 and manual for procurement of works 2019 G.O.I.

Head Assistant

Executive Engineer
Hydraulic Division Uri

NO: HDU/CC-04/ 5022-34

DATED: 21-10-2023

Copy to the:

1 **Mission Director, Mission Directorate Jal Jeevan Mission J&K Civil Secretariat Srianagar/ Jammu for information.**

2 **Chief Engineer Kashmir PHE Department Srinagar for favour of information.**

3 **.District Development Commissioner Baramulla (Chairperson DJJM) for favour information.**

4 **Distt. Superintending Engineer Hydraulic Circle Bla/Bpr HQ Sopore (Member Secretary DJJM) for information. This is with reference to his authorization No:SE/Hyd/DB/5875-88 Dated: 21/08/2023**

5 **Additional District Development Commissioner Baramulla (Member DJJM) for information.**

6 **Assistant Commissioner Development Baramulla (Member DJJM) for information.**

7 **Divisional Forest Officer Baramulla (Member DJJM) for information.**

8 **Chief Planning Officer Baramulla(Member DJJM) for information.**

9 **Chief Medical Officer Baramulla(Member DJJM) for information.**

10 **District Social Welfare Officer Baramulla/ District Tribal Welfare Officer Baramulla(Member DJJM) for information**

11 **District Information Officer Baramulla (Member DJJM) for information.**

12 **Assistant Executive Engineer PHE Sub Division Uri for information.**

13 **File.**

Annexure "A" to the Allotment Order No. 131 of 10 /2023

Retitting of Water Supply Scheme Dudran Bagh Dudran by way of Construction of Intake Chambers/ Protection works, Chain Link fencing, laying and fitting of GI Pipes and other allied works (for providing 100% FHTC) under JJM

S	Particulars	Qty	Unit	Rate	Amount
1	F /W in bulk excavation by manual means over areas (exceeding 30 cm in depth, 1.5m in width, as well as 10 Sqm on plan) including disposal of excavated earth lead upto 50mtr and lift upto 1.5Mtrs as directed by the Engineer Incharge				
1.1	In all kinds of soils(	3335.160	Cum	559.306	**1865374.83**
2	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundation etc in layers not exceeding 20 cm in depth consolidating each deposited layer by ramming and watering lead up to 50m and lift up to 1.5m	2880.531	Cum	206.052	**593538.89**
3	Providing and laying stone soling 2nd class	10.610	Cum	639.207	**6781.98**
4	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centering and shuttering. All work up to plinth level with . 1: 4 : 8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40-mm nominal size)	5.360	Cum	5041.723	**27023.63**
5	Providing and laying in position cement concrete of specified grade including curing but excluding the cost of centring, and shuttering(all work upto plinth level) with. 1 : 2 : 4 (1 cement : 2 coarse sand : 4 graded Stone aggregate 20 mm nominal size)	58.800	Cum	6704.407	**394219.14**
6	Providing and laying in position specified grade of reinforced cement concrete including curing but excluding cost centering shuttering finishing and reinforcement (all work upto plinth level with 1: 1.5 : 3 (1 cement : 1.5 coarse sand : 3 graded stone aggregate 20-mm nominal size)	7.306	Cum	8089.388	**59101.07**
7	Reinforced Cement concrete work in walls (any Thickness) including attached pillasters buttresses, plinth and string courses, fillets, columns, pillars piers, abutments, posts and struts etc. upto floor five level including curing but excluding cost of centering shuttering, finishing and reinforcement with 1:1.5:3 (1cement: 1.5 coarse sand: 3 graded stone aggregate 20mm nominal size.	20.960	Cum	9756.236	**204490.71**
8	Reinforced cement concrete work in beams, suspended floors, roofs having slope upto 15^0 landings, balconies, staircases and spiral staircases upto floor five level including curing but excluding the cost of centering, shuttering, finishing and reinforcement with 1:1.5:3(1Cement: 1.5coarse sand: 3graded stone aggregate 20mm nominal size)	22.199	Cum	10213.771	**226735.50**
9	Centering and shuttering including strutting propping etc. and removal of Form ~~for~~. work for .			0.000	**0.00**
9.1	Foundations, footings, bases of columns etc.	118.740	Sqm	272.005	**32297.89**
9.2	Retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses etc.	83.240	Sqm	595.082	**49534.66**
9.3	Suspended floors, roofs, landings, balconies and access platform.	3.813	Sqm	659.117	**2513.21**
10	12mm cement plaster of mix 1:4 (1-cement: 4-sand)	185.190	Sqm	371.246	**68751.05**
11	Hand-packing stones in wire-crates; including cost of stones and crates and all sorts of carriages of material upto site of work)	146.630	Cum	2592.500	**380138.28**

	Particulars	Qty	Unit	Rate	Amount
12	Providing and mixing water proofing material in cement concrete work in doses by weight of cement as per manufacturer specification	200.000	Kg	70.153	**14030.61**
13	Reinforcement for RCC works including straightening cutting bending, placing in position and binding all complete above plinth level TMT Bars.	3553.790	Kg	90.400	**321264.30**
14	Providing and fixing of tower bolts of 16mm dia , 25cm long full theraded to be mebaded in cement concreate with bolts	80.000	No	207.400	**16592.00**
15	Providing and fixing of MS plate for achoring of over saddel / anchor block with nuts bolts, already fitted in concrete by 4mm thick 200 mm wide and average length 50cm MS plate complete job in all respects.	125.600	Kg	105.919	**13303.45**
16	Providing/fabricating and commissioning of MS Lid for Filtration Plant /Service Reservoir of approved design as per the instructions of Engineer Incharge at site.	76.740	Kg	105.919	**8128.24**
17	Providing and fixing of Sluice Valve (ISI Marked) of approved quality (BIS) including cost of all accessories required and all sorts of carriages of material upto site of work)			0.000	**0.00**
17.1	65mm dia	2.000	Nos	5185.000	**10370.00**
18	Providing and fixing of 8mm thick MS Flanges to GI pipes including cutting of threads welding of flanges to pipe ends including laying and fitting testing and commissioning including cost of nuts, bolts, rubber washers including all carraiges upto site of work complete job.			0.000	**0.00**
18.1	100mm dia	27.000	Joints	1348.100	**36398.70**
18.2	80mm dia	109.000	Joints	1244.400	**135639.60**
18.3	65mm dia	236.000	Joints	1140.700	**269205.20**
18.4	50mm dia	164.000	Joints	1037.000	**170068.00**
18.5	40mm dia	182.000	Joints	933.300	**169860.60**
19	Laying and fitting of GI Pipes excluding trenching and refilling etc.(Including providing and fixing of Pipe Specials/fittings).			0.000	**0.00**
19.1	100mm dia GI pipes	200.000	Mtr	111.685	**22336.98**
19.2	80 mm dia GI pipes	800.000	Mtr	75.753	**60602.28**
19.3	65mm dia	3200.000	mtr	75.753	**242409.12**
19.4	50 mm dia GI pipes	1800.000	Mtr	42.310	**76157.28**
19.5	40 mm dia GI pipes	2000.000	Mtr	42.310	**84619.20**
19.6	25 mm dia GI pipes	2500.000	Mtr	31.784	**79460.13**
19.7	20 mm dia GI pipes	3500.000	Mtr	20.999	**73497.38**
19.8	15 mm dia GI pipes	2000.000	Mtr	20.999	**41998.50**
20	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing Tee, including cutting and threading the pipe etc. complete			0.000	**0.00**
20.1	25 to 40 mm nominal bore	20.000	No	690.901	**13818.03**
20.2	50 to 80 mm nominal bore	4.000	No	1315.694	**5262.78**
21	Carriage of Material from source upto road/dumping site of work by Mechanical Transport including loading unloading and stacking etc complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer			0.000	**0.00**
21.1	Cement and Steel (40-Kms)	19.330	Mton	554.048	**10709.75**
21.2	Sand. (45-Kms)	21.343	Cum	674.766	**14401.52**
21.3	Agg. 20mm (70-Kms)	35.300	Cum	932.356	**32912.18**
21.4	Stone Soling 07-Kms)	4.230	Cum	288.047	**1218.44**
21.5	Agg. 40mm (70-Kms)	4.820	Cum	1013.377	**4884.48**
21.6	Pipes 40 Km	65.440	Mton	554.048	**36256.92**

	Particulars	Qty	Unit	Rate	Amount
21.7	Carraige of chain link fencing (40KM)	1.380	Mton	554.048	764.59
	Carriage of material from road/dumping site to actual site of work by manual labours/ponies including loading unloading and safe stacking etc Complete and shall be paid strictly as per SSR of Rates 2020 and distance as per actual duly recommended by Junior Engineer/Assistant Executive Engineer (4000 Mtrs)			0.000	0.00
22.1	Cement	15.490	Mton	1587.284	24587.03
22.2	Steel	3.541	Mton	3409.884	12074.40
22.3	Sand	21.343	Cum	3961.630	84553.08
22.4	Agg 20mm	35.300	Cum	3961.630	139845.55
22.5	Agg 40mm	4.820	Cum	4282.603	20642.14
22.6	Pipes	65.440	Mton	2001.700	130991.27
22.7	Carraige of chain link fencing	1.380	Mton	554.048	764.59
22.8	Stone Soling (500-Mtrs)	4.230	Cum	757.840	3205.66
				Total	6293334.81

Rupees Sixty Two Lakh(s) Ninety Three Thousand Three Hundred Thirty Four And Paise Eighty One Only

Checked by

Head D/Man

Executive Engineer
Hydraulic Division Uri